



**DEPARTMENT OF TRANSPORTATION  
STATE OF GEORGIA  
PROJECT CONCEPT REPORT**

Project Type: <u>Culvert Replacement</u>	P.I. Number: <u>0011677</u>
GDOT District: <u>District 1</u>	County: <u>Jackson</u>
Federal Route Number: <u>N/A</u>	State Route Number: <u>11</u>
Project Number: _____	N/A

*The existing triple barrel bridge culvert is currently in a deteriorated state and is to be replaced. Along with the replacement of the bridge culvert the existing roadway will be brought up to standard, mainly with the addition of guardrail.*

Submitted for approval: *\* Submissions on file*

<i>C. J. ...</i>	<u>5/27/2014</u>
GDOT Concept/Design Phase Office Head & Office	DATE
<i>For</i> <i>Hiral Patel /KLP</i>	<u>2/25/2014</u>
State Program Delivery Engineer	DATE
<i>* Charles Robinson /KLP</i>	<u>2/25/2014</u>
GDOT Project Manager	DATE

*\*\* Recommendations on file*  
Recommendation for approval:

Program Control Administrator	DATE
<i>** Glenn Bowman /KLP</i>	<u>3/5/2014</u>
State Environmental Administrator	DATE
<i>** Kathy Zahul /KLP</i>	<u>2/28/2014</u>
State Traffic Engineer	DATE
<i>** Lisa Myers /KLP</i>	<u>2/28/2014</u>
Project Review Engineer	DATE
<i>** Jun BimKammer /KLP</i>	<u>3/3/2014</u>
<i>For</i> State Utilities Engineer	DATE
<i>** Bayne Smith /KLP</i>	<u>3/4/2014</u>
District Engineer	DATE
<i>** Ben Rabun /KLP</i>	<u>2/28/2014</u>
State Bridge Design Engineer	DATE


State Transportation Financial Management Administrator

DATE

The concept as presented herein and submitted for approval is consistent with that which is included in the Regional Transportation Plan (RTP) and/or the State Transportation Improvement Program (STIP).

<i>** Cynthia VanDyke</i>	<u>3/17/2014</u>
State Transportation Planning Administrator	DATE

### PROJECT LOCATION MAP



## Project Location Map

Bridge Culvert Replacement on SR 11 at Mulberry River Tributary  
Jackson County

### PLANNING AND BACKGROUND

**Project Justification Statement:** This bridge culvert was built in 1938. This is a three barrel reinforced concrete box bridge culvert that is 50 feet long. Each barrel is ten feet high and ten feet wide. This bridge culvert is in poor condition with settlement cracks that are causing fill to be lost and voids formed above the roof of the bridge culvert. The roadway has settled above those cracks and has started to crack. Due to the poor condition of the bridge culvert and the roadway settlement taking place replacement of this structure is recommended.

**Existing conditions:** The current roadway consists of 12 ft travel lanes with 6 ft shoulders. Existing utilities consist of a water line to the east, a fiber optic line to the west, and a telephone line to the west.

**Other projects in the area:**

- 0007663
  - SR 124 FM CR 171/JOSH PIRKLE ROAD TO SR 11/US 129: Reconstruction/Rehabilitation
- 0008434
  - SR 53 FROM I-85 TO CR 167/TAPP WOOD ROAD: Reconstruction/Rehabilitation
- M004206
  - SR 11 @ 1 LOC; SR 53 @ 1 LOC & SR 246 @ 1 LOC - DECK REHAB
- M004299
  - SR 53 FROM JACKSON COUNTY LINE TO SR 11: Maintenance

**MPO:** N/A - Project not in MPO

MPO Project ID N/A

**Regional Commission:** Northeast Georgia RC

RC Project ID N/A

**Congressional District(s):** 9

**Federal Oversight:**  Full Oversight  Exempt  State Funded  Other

**Projected Traffic:** AADT

Current Year (2012): 4500 Open Year (2019): 4800  
Traffic Projections Performed by: Office of Planning

Design Year (2039): 5800

**Functional Classification (Mainline):** Rural Minor Arterial

**Complete Streets - Bicycle, Pedestrian, and/or Transit Warrants:**

Warrants met:  None  Bicycle  Pedestrian  Transit

**Is this a 3R (Resurfacing, Restoration, & Rehabilitation) Project?**  No  Yes

**Pavement Evaluation and Recommendations**

Preliminary Pavement Evaluation Summary Report Required?  No  Yes  
 Preliminary Pavement Type Selection Report Required?  No  Yes  
 Feasible Pavement Alternatives:  HMA  PCC  HMA & PCC

**DESIGN AND STRUCTURAL**

**Description of the proposed project:** The proposed project replaces the existing 50 ft. triple barrel bridge culvert with a 100 ft. triple barrel bridge culvert. The entire length of the project is 0.14 miles. Both the existing and proposed triple barrel bridge culverts are 10 feet by 10 feet per barrel. The existing alignment is to be utilized for final construction. A reduced shoulder width of 8 ft. will be used and a shoulder of 13.5 ft. will be used to accommodate guardrail. An off-site detour will be used to allow the culvert to be replaced with an open cut. The road will continue to be a rural two lane, 55 mph corridor.

**Major Structures:**

Structure	Existing	Proposed
ID # and/or Location	50 ft. long, 10 ft. high and 10 ft. wide, 3 barrel, concrete, poor condition	100 ft. long, 10 ft. high and 10 ft. wide, 3 barrel, concrete
Retaining walls		
Other		

**Mainline Design Features: SR 11/ Rural Minor Arterial**

Feature	Existing	Standard*	Proposed
<b>Typical Section</b>			
- Number of Lanes	2	2	2
- Lane Width(s)	12 ft	12 ft	12 ft
- Median Width & Type	n/a	n/a	n/a
- Outside Shoulder or Border Area Width	6', 2' paved	10'	8', 4' paved
- Outside Shoulder Slope	6%	6%	6%
- Inside Shoulder Width	n/a	n/a	n/a
- Sidewalks	n/a	n/a	n/a
- Auxiliary Lanes	n/a	n/a	n/a
- Bike Lanes	n/a	n/a	n/a
Posted Speed	55 mph		55 mph
Design Speed	n/a	55 mph	55 mph
Min Horizontal Curve Radius	n/a	1060 ft	800 ft
Superelevation Rate	10%	6% or 8% max	10% max
Grade	5.1%	6%	5.24%
Access Control	Permitted	Permitted	Permitted
Right-of-Way Width	60 ft		206 ft
Maximum Grade – Crossroad	n/a	n/a	n/a
Design Vehicle	SU	SU	SU

\*According to current GDOT design policy if applicable

**Major Interchanges/Intersections: N/A**

**Lighting required:**  No  Yes

If lighting is included in the project, attach lighting agreements or commitment letters.

**Off-site Detours Anticipated:**  No  Undetermined  Yes

**Transportation Management Plan [TMP] Required:**  No  Yes  
 If Yes: Project classified as:  Non-Significant  Significant  
 TMP Components Anticipated:  TTC  TO  PI

**Design Exceptions to FHWA/AASHTO controlling criteria anticipated:**

FHWA/AASHTO Controlling Criteria	No	Undeter- -mined	Yes	Appvl Date (if applicable)
1. Design Speed	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
2. Lane Width	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
3. Shoulder Width	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
4. Bridge Width	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
5. Horizontal Alignment	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
6. Superelevation	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
7. Vertical Alignment	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
8. Grade	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
9. Stopping Sight Distance	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
10. Cross Slope	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
11. Vertical Clearance	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
12. Lateral Offset to Obstruction	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
13. Bridge Structural Capacity	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	

The Horizontal Alignment and Superelevation Exceptions may not be required due to the substandard components are located where the project ties into existing.

**Design Variances to GDOT Standard Criteria anticipated:**

GDOT Standard Criteria	Reviewing Office	No	Undeter- -mined	Yes	Appvl Date (if applicable)
1. Access Control - Median Opening Spacing	DP&S	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
2. Median Usage & Width	DP&S	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
3. Intersection Skew Angle	DP&S	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
4. Lateral Offset to Obstruction	DP&S	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
5. Intersection Sight Distance	DP&S	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
6. Bike, Pedestrian & Transit Accommodations	DP&S	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
7. GDOT Drainage Manual	DP&S	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
8. Georgia Standard Drawings	DP&S	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
9. GDOT Bridge & Structural Manual	Bridge Design	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
10. Roundabout Illumination	DP&S	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	

VE Study anticipated:  No       Yes       Completed – Date:

### UTILITY AND PROPERTY

Temporary State Route needed:  No  Yes  Undetermined

Railroad Involvement: N/A

Utility Involvements: Water (Jackson County), Telephone Line, Fiber Optic Line

SUE Required:  No  Yes  Undetermined

Public Interest Determination Policy and Procedure recommended (Utilities)?  No  Yes

Right-of-Way (ROW): Existing width: 60 ft Proposed width: 206 ft

Required Right-of-Way anticipated:  None  Yes  Undetermined

Easements anticipated:  None  Temporary  Permanent  Utility  Other

*Check all easement types that apply.*

Anticipated total number of impacted parcels:	4
Displacements anticipated:	
Businesses:	0
Residences:	0
Other:	0
Total Displacements:	0

Location and Design approval:  Not Required  Required

### CONTEXT SENSITIVE SOLUTIONS

Issues of Concern: N/A

Context Sensitive Solutions Proposed: N/A

**ENVIRONMENTAL & PERMITS**

**Anticipated Environmental Document:**

GEPA:  NEPA:  CE  EA/FONSI  EIS

MS4 Permit Compliance – Is the project located in a MS4 area?  No  Yes

**Environmental Permits/Variations/Commitments/Coordination anticipated:**

Permit/ Variance/ Commitment/ Coordination Anticipated	No	Yes	Remarks
1. U.S. Coast Guard Permit	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
2. Forest Service/Corps Land	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
3. CWA Section 404 Permit	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
4. Tennessee Valley Authority Permit	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
5. Buffer Variance	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
6. Coastal Zone Management Coordination	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
7. NPDES	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
8. FEMA	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
9. Cemetery Permit	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
10. Other Permits	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
11. Other Commitments	<input type="checkbox"/>	<input checked="" type="checkbox"/>	See Environmental Commitment Sheet
12. Other Coordination	<input type="checkbox"/>	<input type="checkbox"/>	

Is a PAR required?  No  Yes  Completed – Date:

**Environmental Comments and Information:**

**NEPA/GEPA:** A Categorical Exclusion will be prepared. There are no known or suspected 4(f) resources.

**Ecology:** The ecology resource survey has been completed and the draft report has been prepared. There is one perennial stream, one intermittent stream, and three ephemeral, non-buffered state waters. There is potential habitat for one aquatic protected species. An additional species survey will be completed.

**History:** The historic resource survey has been completed and the draft report has been prepared. No significant resources were located within the APE. SHPO concurrence is expected.

**Archeology:** The archaeological survey has been completed, and a short form report drafted. No archaeological resources, including cemeteries, were located within the APE. SHPO concurrence is expected.

**Air & Noise:** The project is not located in a non-attainment area; therefore no ozone or hotspot analysis will be required. A Type III noise assessment with no modeling required will be prepared for this project.

**Public Involvement:** An off-site detour is proposed for this project. A detour public meeting will be required.

**Major stakeholders:** The major stakeholders are the residents of Jackson County and the traveling public.

**Project Air Quality:**

Is the project located in a PM 2.5 Non-attainment area?  No  Yes  
 Is the project located in an Ozone Non-attainment area?  No  Yes  
 Is a Carbon Monoxide hotspot analysis required?  No  Yes

**CONSTRUCTION**

**Issues potentially affecting constructability/construction schedule:** Contractor may need area in potential ESA for equipment during construction of the culvert replacement.

**Early Completion Incentives recommended for consideration:**  No  Yes

**COORDINATION, ACTIVITIES, RESPONSIBILITIES, AND COSTS**

**Initial Concept Meeting:** N/A

**Concept Meeting:** 12/17/13

**Other coordination to date:** TBD

<b>Project Activity</b>	<b>Party Responsible for Performing Task(s)</b>
Concept Development	District 1 Design
Design	District 1 Design
Right-of-Way Acquisition	District 1 ROW
Utility Relocation	GDOT D1 Coord/Utility Companies Relocate
Letting to Contract	GDOT
Construction Supervision	District 1 Construction
Providing Material Pits	Contractor
Providing Detours	GDOT/Contractor
Environmental Studies, Documents, and Permits	GDOT/Contractor
Environmental Mitigation	GDOT
Construction Inspection & Materials Testing	District 1 Construction

**Project Cost Estimate Summary and Funding Responsibilities:**

	<b>Breakdown of PE</b>	<b>ROW</b>	<b>Reimbursable Utility</b>	<b>CST*</b>	<b>Environmental Mitigation</b>	<b>Total Cost</b>
Funded By	GDOT	GDOT	GDOT	GDOT	GDOT	
\$ Amount	\$ 421,685	\$ 138,000	\$ 0	\$ 595,560**	\$ 58,500	\$ 1,213,745
Date of Estimate	3/4/2013	6/3/2014	1/17/2014	5/23/2014	4/2/2014	

\* CST Cost includes: Construction, Engineering and Inspection, Construction Contingency and Liquid AC Cost Adjustment.

\*\*Construction estimate is based on a cast in place alternate. However, project will be investigated for precast alternate design/bidding which may reduce costs further.

**ALTERNATIVES DISCUSSION**

**Alternative selection:** Off-Site Detour

<b>Preferred Alternative: Off-Site Detour</b>			
<b>Estimated Property Impacts:</b>	4	<b>Estimated Total Cost:</b>	\$1,213,745
<b>Estimated ROW Cost:</b>	\$138,000	<b>Estimated CST Time:</b>	4 mo.
<b>Rationale:</b> The Layout provides minimal impact of ROW, earthwork, and utilities. Main cost is construction of the bridge culvert. Detour length is a total of 14.7 miles.			

<b>Alternative 1: On-site Detour</b>			
<b>Estimated Property Impacts:</b>	5	<b>Estimated Total Cost:</b>	\$1,481,513
<b>Estimated ROW Cost:</b>	\$156,000	<b>Estimated CST Time:</b>	6 mo.
<b>Rationale:</b> The layout provides minimal impact of ROW, earthwork, and utilities. Detour consists of a single travel lane operated with a temporary signal.			

<b>Alternative 2: Existing Alignment, Existing Horizontal Curve redesigned to current standards</b>			
<b>Estimated Property Impacts:</b>	5	<b>Estimated Total Cost:</b>	\$1,559,972
<b>Estimated ROW Cost:</b>	\$113,650	<b>Estimated CST Time:</b>	6 mo.
<b>Rationale:</b> Additional costs due to redesigning the existing horizontal curve. Adjusting the curve is questionably beyond scope of project.			


<b>Alternative 3: 48' Horizontal Alignment Offset to West. Use combination of existing 2-lane roadway and proposed 2-lane roadway for on-site detour.</b>			
<b>Estimated Property Impacts:</b>	5	<b>Estimated Total Cost:</b>	\$1,728,554
<b>Estimated ROW Cost:</b>	\$115,600	<b>Estimated CST Time:</b>	6 mo.
<b>Rationale:</b> Additional construction costs for this alternative may prove to be too costly.			

<b>Alternative 4: Off-Site Detour with improved profile (meeting criteria for 45 mph) at project location.</b>			
<b>Estimated Property Impacts:</b>	4	<b>Estimated Total Cost:</b>	\$1,483,654
<b>Estimated ROW Cost:</b>	\$154,000	<b>Estimated CST Time:</b>	5 mo.
<b>Rationale:</b> Additional construction costs for this alternative may prove to be too costly.			

**LIST OF ATTACHMENTS/SUPPORTING DATA**

- 1. Concept Layout
- 2. Typical sections
- 3. Detailed Cost Estimates:
  - a. Total Construction Cost Summary
  - b. Construction including Engineering and Inspection
  - c. Completed Fuel & Asphalt Price Adjustment forms
  - d. Right-of-Way
  - e. Utility Cost Estimate
  - f. Environmental Mitigation Estimate
- 4. Crash summaries
- 5. Traffic Counts
- 6. Bridge Inventory
- 7. Concept Meeting Minutes
- 8. Phone Conversation Minutes with Jackson County
- 9. E-mail Chain with Glenn Bowman regarding preferred alternate


**APPROVALS**

Concur:   
Director of Engineering

Approve:   
Chief Engineer

6/23/14  
Date

PI: 0011677 Jackson County  
 SR 11 @ Mulberry Tributary  
 Concept Layout  
 Off-Site Detour



**ALLOWABLE RANGES TABLE**

FOR THIS PROJECT, CROSS SLOPES THAT ARE ADJUSTED TO "BEST FIT" EXISTING PAVEMENT SLOPES ARE SUBJECT TO THE FOLLOWING LIMITS:

**A. NORMAL CROWN**

SECTION WITH GRADES 0.5% OR GREATER	SECTION WITH GRADES LESS THAN 0.5%
0.0150 FT/FT - MINIMUM	0.0156 FT/FT - MINIMUM
0.0208 FT/FT - DESIRABLE	0.0208 FT/FT - DESIRABLE
0.0250 FT/FT - MAXIMUM	0.0300 FT/FT - MAXIMUM

**B. SUPERELEVATION RATE**

S.E. RATE SHOWN ON PLANS OR SE RATE EXISTING IN FIELD, WHICHEVER IS GREATER.

**C. SUPERELEVATION TRANSITION LENGTH (LENGTH FROM FLAT POINT TO FULL SE)**

RATE OF CHANGE	CORRESPONDING DIFFERENCE IN GRADE BETWEEN PIVOT POINT AND EDGE OF PAVEMENT
MINIMUM 1:150	0.67%
DESIRABLE 1:200	0.50%
MAXIMUM 1:300	0.33%



LENGTH SHALL BE SET TO AVOID CREATING A FLAT GUTTER GRADE ON LOW SIDE AND TO AVOID FLAT CROSS SLOPES AT OR NEAR THE LOW POINT OF VERTICAL CURVES.

**D. POSITIONING OF SUPERELEVATION TRANSITION LENGTH ON SIMPLE CURVES**

50% OF TRANSITION INSIDE CURVE - MAXIMUM
33% OF TRANSITION INSIDE CURVE - DESIRABLE
20% OF TRANSITION INSIDE CURVE - MINIMUM

NOTE: CROWN WIPE-OUT SHALL BE AT THE SAME RATE AS THE SE TRANSITION.



**E. SMOOTHING OF BREAKS IN EDGE PROFILE AT BEGIN AND END OF TRANSITION SHALL BE ACCOMPLISHED BY VERTICAL CURVE WITH A MINIMUM LENGTH (1 IN FEET) EQUAL TO THE SPEED DESIGN (IN MPH).**



- ④ 9.5 mm SUPERPAVE, TYPE II, GP 2 ONLY, INCL BITUM MATL AND H LIME, 135 LB/SY
- ⑤ 19 mm SUPERPAVE, GP 1 OR II, INCL BITUM MATL AND H LIME, 220 LB/SY
- ⑥ 25 mm SUPERPAVE, GP 1 OR II, INCL BITUM MATL AND H LIME, 440 LB/SY
- ⑦ GRADED AGGREGATE BASE COURSE, INCL MATL, 12 IN

SLOPE CONTROLS		
SLOPE	CUT	FILL
4:1	—	0-10'
2:1	ALL	OVER 10'

S.E. RATE	SHOULDER SLOPE
2.0% OR 3.0%	4.0%
4.0% OR 5.0%	2.0%
6.0% OR 7.0%	1.0%
8.0% +	0.0%



SAFETY EDGE TREATMENT SHALL BE FOLLOWED FOR THE OUTSIDE EDGE OF ALL INCLUDED PAVEMENTS WHETHER EDGE OF TRAVEL LANE OR SHOULDER (EXCLUDING PAVEMENT BEHIND GUARDRAIL) SEE CONST DETAIL P-1 FOR DETAILS



REVISION DATES

NO.	DATE	DESCRIPTION

STATE OF GEORGIA  
 DEPARTMENT OF TRANSPORTATION  
 OFFICE: DISTRICT ONE DESIGN  
**TYPICAL SECTIONS**

SR11 @ MULBERRY RIVER TRIB.  
 JACKSON COUNTY

DRAWING NO.  
**05-001**

## Project Cost Estimate Summary

PI 0011677, Jackson County

### Construction:

Construction Cost Estimate	\$	554,787.66
Engineering and Inspection (5%)	\$	27,739.38
Total Liquid AC Adjustment	\$	<u>13,032.56</u>
Subtotal	\$	595,559.60

### Total Costs:

PE Costs:	\$	421,685.00
Right of Way Costs:	\$	138,000.00
Utilities:	\$	0.00
Construction:	\$	595,560.00
Environmental Mitigation:	\$	<u>58,500.00</u>
Total Project Costs:	\$	1,213,745.00

# DETAILED COST ESTIMATE



**Job: 0011677**

JOB NUMBER 0011677

FED/STATE PROJECT NUMBER 0011677

SPEC YEAR: 01

DESCRIPTION: SR 11 @ MULBERRY RIVER TRIBUTARY 6.3 MI SW OF JEFFERSON

**ITEMS FOR JOB 0011677**

**0010 - ROADWAY**

Line Number	ITEM	QUANTITY	UNITS	PRICE	DESCRIPTION	AMOUNT
0035	150-1000	1.000	LS	\$60,000.00000	TRAFFIC CONTROL - NA	\$60,000.00
0040	210-0100	1.000	LS	\$66,221.26000	GRADING COMPLETE - NA	\$66,221.26
0020	310-1101	778.520	TN	\$22.42717	GR AGGR BASE CRS, INCL MATL	\$17,460.00
0005	402-3100	280.960	TN	\$93.35312	REC AC 9.5 MM SP,TPI,GP1ORBL1,INCL BM&HL	\$26,228.49
0015	402-3121	229.440	TN	\$84.19448	RECYL AC 25MM SP,GP1/2,BM&HL	\$19,317.58
0010	402-3190	253.860	TN	\$87.14380	RECYL AC 19 MM SP,GP 1 OR 2 ,INC BM&HL	\$22,122.33
0085	413-1000	117.280	GL	\$4.06134	BITUM TACK COAT	\$476.31
0090	641-1200	971.550	LF	\$15.96283	GUARDRAIL, TP W	\$15,508.69
0095	641-5001	2.000	EA	\$641.56417	GUARDRAIL ANCHORAGE, TP 1	\$1,283.13
0100	641-5012	4.000	EA	\$1,840.54512	GUARDRAIL ANCHORAGE, TP 12	\$7,362.18
<b>SUBTOTAL FOR ROADWAY:</b>						<b>\$235,979.97</b>

**0030 - EROSION CONTROL**

Line Number	ITEM	QUANTITY	UNITS	PRICE	DESCRIPTION	AMOUNT
0075	163-0528	400.000	LF	\$3.39000	CONSTR AND REM FAB CK DAM -TP C SLT FN	\$1,356.00
0065	163-0541	8.000	EA	\$297.02932	CONSTR & REM ROCK FILTER DAMS	\$2,376.23
0055	165-0030	1584.000	LF	\$0.54981	MAINT OF TEMP SILT FENCE, TP C	\$870.90
0080	165-0041	400.000	LF	\$1.19576	MAINT OF CHECK DAMS - ALL TYPES	\$478.30
0070	165-0110	8.000	EA	\$110.13629	MAINT OF ROCK FILTER DAM	\$881.09
0060	171-0030	1584.000	LF	\$2.79193	TEMPORARY SILT FENCE, TYPE C	\$4,422.42
<b>SUBTOTAL FOR EROSION CONTROL:</b>						<b>\$10,384.94</b>

**0040 - CULVERT**

Line Number	ITEM	QUANTITY	UNITS	PRICE	DESCRIPTION	AMOUNT
0025	500-3101	527.120	CY	\$506.73081	CLASS A CONCRETE	\$267,107.94
0030	511-1000	59282.000	LB	\$0.65904	BAR REINF STEEL	\$39,069.21
<b>SUBTOTAL FOR CULVERT:</b>						<b>\$306,177.15</b>

**0050 - SIGNING & MARKING**

Line Number	ITEM	QUANTITY	UNITS	PRICE	DESCRIPTION	AMOUNT
0105	653-1501	1746.000	LF	\$0.57667	THERMO SOLID TRAF ST 5 IN, WHI	\$1,006.87
0110	653-1502	1746.000	LF	\$0.57824	THERMO SOLID TRAF ST, 5 IN YEL	\$1,009.61
0115	654-1001	44.000	EA	\$5.20724	RAISED PVMT MARKERS TP 1	\$229.12
<b>SUBTOTAL FOR SIGNING &amp; MARKING:</b>						<b>\$2,245.60</b>

**TOTALS FOR JOB 0011677**

# DETAILED COST ESTIMATE



Job: 0011677

<b>ITEMS COST:</b>	<b>\$554,787.66</b>
<b>COST GROUP COST:</b>	<b>\$0.00</b>
<b>ESTIMATED COST:</b>	<b>\$554,787.66</b>
<b>CONTINGENCY PERCENT:</b>	<b>0.00</b>
<b>ENGINEERING AND INSPECTION:</b>	<b>0.00</b>
<b>ESTIMATED COST WITH CONTINGENCY AND E&amp;I:</b>	<b>\$554,787.66</b>

PROJ. NO. [Redacted]  
 P.I. NO. 0011677  
 DATE 10/13/2013

CALL NO.

INDEX (TYPE)	DATE	INDEX
REG. UNLEADED	Oct-13	\$ 3.692
DIESEL		\$ 3.931
LIQUID AC		\$ 561.00

Link to Fuel and AC Index:  
<http://www.dot.ga.gov/doingbusiness/Materials/Pages/asphaltcementindex.aspx>

**LIQUID AC ADJUSTMENTS**

PA=[((APM-APL)/APL)]xTMTxAPL

**Asphalt**

Price Adjustment (PA)				<b>12863.0007</b>	\$	<b>12,863.00</b>
Monthly Asphalt Cement Price month placed (APM)	Max. Cap	60%	\$	897.60		
Monthly Asphalt Cement Price month project let (APL)			\$	561.00		
<b>Total Monthly Tonnage of asphalt cement (TMT)</b>				<b>38.2145</b>		

ASPHALT	Tons	%AC	AC ton
Leveling		5.0%	0
12.5 OGFC		5.0%	0
12.5 mm		5.0%	0
9.5 mm SP	281	5.0%	14.0485
25 mm SP	229	5.0%	11.4725
19 mm SP	254	5.0%	12.6935
	<b>764.29</b>		<b>38.2145</b>

**BITUMINOUS TACK COAT**

Price Adjustment (PA)				\$	<b>169.56</b>	\$	<b>169.56</b>
Monthly Asphalt Cement Price month placed (APM)	Max. Cap	60%	\$	897.60			
Monthly Asphalt Cement Price month project let (APL)			\$	561.00			
<b>Total Monthly Tonnage of asphalt cement (TMT)</b>				<b>0.503729436</b>			

Bitum Tack

Gals	gals/ton	tons
117	232.8234	0.50372944

**BITUMINOUS TACK COAT (surface treatment)**

Price Adjustment (PA)				<b>0</b>	\$	<b>-</b>
Monthly Asphalt Cement Price month placed (APM)	Max. Cap	60%	\$	897.60		
Monthly Asphalt Cement Price month project let (APL)			\$	561.00		
<b>Total Monthly Tonnage of asphalt cement (TMT)</b>				<b>0</b>		

Bitum Tack	SY	Gals/SY	Gals	gals/ton	tons
Single Surf. Trmt.		0.20	0	232.8234	0
Double Surf.Trmt.		0.44	0	232.8234	0
Triple Surf. Trmt		0.71	0	232.8234	0

**TOTAL LIQUID AC ADJUSTMENT \$ 13,032.56**

**GEORGIA DEPARTMENT OF TRANSPORTATION  
PRELIMINARY ROW COST ESTIMATE SUMMARY**

Date: 6/3/2014 Project: 0011677  
 Revised: County: Jackson  
 PI: 0011677

Description: SR 11 @ Mulberry Tributary  
 Project Termini: SR 11 @ Mulberry Tributary

Existing ROW: Varies  
 Required ROW: Varies  
 Parcels: 4

Land and Improvements \_\_\_\_\_ \$45,746.25

Proximity Damage	\$0.00
Consequential Damage	\$0.00
Cost to Cures	\$0.00
Trade Fixtures	\$0.00
Improvements	\$10,000.00

Valuation Services \_\_\_\_\_ \$8,000.00

Legal Services \_\_\_\_\_ \$40,200.00

Relocation \_\_\_\_\_ \$8,000.00

Demolition \_\_\_\_\_ \$0.00

Administrative \_\_\_\_\_ \$35,500.00

TOTAL ESTIMATED COSTS \_\_\_\_\_ \$137,446.25

**TOTAL ESTIMATED COSTS (ROUNDED) \_\_\_\_\_ \$138,000.00**

Preparation Credits	Hours	Signature

Prepared By: Dashone Alexander CG#: 286999 06/03/2014  
 Approved By: Dashone Alexander CG#: 286999 06/03/2014

**NOTE: No Market Appreciation is included in this Preliminary Cost Estimate**

**DEPARTMENT OF TRANSPORTATION  
STATE OF GEORGIA**

**INTERDEPARTMENT CORRESPONDENCE**

**FILE** P.I. No. 0011677 Jackson OFFICE Gainesville  
SR 11 @ Mulberry River Tributary  
6.3 miles SW of Jefferson DATE January 17, 2014

**FROM** Nathaniel O'Kelley   
Assistant District Utilities Engineer

**TO** Charles A. Robinson, Project Manager

**SUBJECT** PRELIMINARY UTILITY COST ESTIMATE

As requested by your office, we are furnishing you with a Preliminary Utility Cost estimate for the subject project.

FACILITY OWNER	NON-REIMBURSABLE	REIMBURSABLE
Jackson County Water	\$ 16,228.00	\$ 0.00
Windstream Comm. (Telephone)	\$ 14,028.00	\$ 0.00
<b>TOTAL</b>	<b>\$ 30,256.00</b>	<b>\$ 0.00</b>

If you have any questions, please contact Nathaniel O'Kelley at 770-532-5510.

HNO:hno

C: Mike Boiden, State Utilities Engineer  
Angie Robinson, Office of Financial Management  
Dana Garrison, Area Engineer  
Nicholas Ryan Mullins, District 1 Design  
File

## Houppermans, Colin

---

**From:** Robinson, Charles A.  
**Sent:** Wednesday, April 02, 2014 4:22 PM  
**To:** Houppermans, Colin  
**Cc:** Lott, Justin  
**Subject:** FW: PI 0011677, Jackson County - ENVE.DGN file

Hi Colin,

Please note that I have been informed that the environmental mitigation costs for the above referenced project have been estimated at \$58,500 as indicated in email below. Please include this amount in the concept report.

Please let me know if you have any questions.

Thanks,

### **Charles A. Robinson**

Project Manager  
Georgia Department of Transportation  
Office of Program Delivery  
One Georgia Center  
600 West Peachtree Street, Floor 25  
Atlanta, GA 30308  
Office: (404) 631-1439  
Mobile: (404) 985-0720  
Fax: (404) 631-1588  
[chrobinson@dot.ga.gov](mailto:chrobinson@dot.ga.gov)

---

**From:** Lenor Bromberg [mailto:lbromberg@keagroup.com]  
**Sent:** Wednesday, April 02, 2014 4:12 PM  
**To:** Robinson, Charles A.  
**Cc:** Jon Russell  
**Subject:** Fwd: PI 0011677, Jackson County - ENVE.DGN file

Charles -

In the email below please find the estimated mitigation costs as well as the basis for this cost.

Please let us know if you have any questions.

Thank you!

-Lenor

Lenor M. Bromberg, PE, AVS  
Associate VP - Environmental & Design  
KEA Group  
770-500-9605 cell

Begin forwarded message:

**From:** "Jon Russell" <[jrussell@keagroup.com](mailto:jrussell@keagroup.com)>  
**Date:** April 2, 2014 at 3:27:46 PM EDT  
**To:** "Lenor Bromberg" <[lbromberg@keagroup.com](mailto:lbromberg@keagroup.com)>  
**Subject:** RE: PI 0011677, Jackson County - ENVE.DGN file

In the concept report drawing it shows the new culvert being 97', so we can estimate 120' of stream impact. Using a very basic multiplier, 780 credits would be required, costing around \$58,500.

If I don't see you respond in the next while I will pass it along to Charles.

-Jon

**Kennedy Engineering & Associates Group LLC**  
*Exceptional People, Exceptional Service, Exceptional Solutions*

678-904-8591 ext. 26  
845-596-1953 - cell

---

**From:** Lenor Bromberg [<mailto:lbromberg@keagroup.com>]  
**Sent:** Wednesday, April 02, 2014 2:59 PM  
**To:** Jon Russell  
**Subject:** Fwd: PI 0011677, Jackson County - ENVE.DGN file

Jon,

Can you please take a quick stab at potential impacts and mitigation cost for the Jackson project and let me know what you think?

Thank you!

-Lenor

Lenor M. Bromberg, PE, AVS  
Associate VP - Environmental & Design  
KEA Group  
770-500-9605 cell

Begin forwarded message:

**From:** "Robinson, Charles A." <[chrobinson@dot.ga.gov](mailto:chrobinson@dot.ga.gov)>  
**Date:** April 2, 2014 at 2:47:43 PM EDT  
**To:** 'Lenor Bromberg' <[lbromberg@keagroup.com](mailto:lbromberg@keagroup.com)>  
**Cc:** "Houppermans, Colin" <[chouppermans@dot.ga.gov](mailto:chouppermans@dot.ga.gov)>, "Lott, Justin" <[JLott@dot.ga.gov](mailto:JLott@dot.ga.gov)>, 'Tommy Crochet' <[tcrochet@mcgeepartners.com](mailto:tcrochet@mcgeepartners.com)>, "[jrussell@keagroup.com](mailto:jrussell@keagroup.com)" <[jrussell@keagroup.com](mailto:jrussell@keagroup.com)>  
**Subject:** RE: PI 0011677, Jackson County - ENVE.DGN file

### Crash Data

JACKSON COUNTY, SR 11 milelogs 0.51 - 1.75

Accident No	Date	Time	County	Route Type	Route	Milelog	Intersecting RT Type	Intersecting Rt	Injuries	Fatalities	Harmful Event	Collision	Location of Impact	Light	Surface	DirVeh1	DirVeh2	MnvrVeh1	MnvrVeh2
'84930284	11/16/2008	8:36 PM	Jackson	State Route	'001100	0.53		'	0	0	Deer	Not A Collision With A Motor Vehicle	On Roadway	Dark-Not Lighted	Dry	S		Straight	
'70310266	1/7/2007	4:30 PM	Jackson	State Route	'001100	0.67		'	2	0	Tree	Not A Collision With A Motor Vehicle	Off Roadway	Daylight	Wet	S		Negotiating a Curve	
'65110721	12/26/2006	7:12 AM	Jackson	State Route	'001100	0.68		'	1	0	Tree	Not A Collision With A Motor Vehicle	Off Roadway	Dark-Not Lighted	Wet	N		Negotiating a Curve	
'74940380	10/27/2007	12:15 PM	Jackson	State Route	'001100	0.68		'	0	0	Motor Vehicle in Motion	Rear End	On Roadway	Daylight	Dry	N	N	Negotiating a Curve	Turning Right
'90350466	1/27/2009	6:30 AM	Jackson	State Route	'001100	0.68		'	4	0	Motor Vehicle in Motion	Head On	On Roadway	Dark-Not Lighted	Dry	N	S	Negotiating a Curve	Negotiating a Curve
'50200741	1/5/2005	6:35 PM	Jackson	State Route	'001100	0.73		'	0	0	Motor Vehicle in Motion	Sideswipe - Same Direction	On Roadway	Dark-Not Lighted	Dry	S	S	Straight	Straight
'53010469	7/21/2005	11:34 AM	Jackson	State Route	'001100	0.88		'	1	0	Tree	Not A Collision With A Motor Vehicle	Off Roadway	Daylight	Dry	E		Negotiating a Curve	
'84930270	11/12/2008	6:27 PM	Jackson	State Route	'001100	0.88		'	0	0	Tree	Not A Collision With A Motor Vehicle	Off Roadway	Dark-Not Lighted	Dry	N		Straight	
'55190479	11/21/2005	3:15 PM	Jackson	State Route	'001100	0.98		'	0	0	Other Non-Collision	Not A Collision With A Motor Vehicle	Off Roadway	Daylight	Wet	N		Negotiating a Curve	
'94180356	9/22/2009	1:11 AM	Jackson	State Route	'001100	1.26		'	2	0	Embankment	Not A Collision With A Motor Vehicle	Off Roadway	Dark-Lighted	Wet	N		Straight	
'72180521	5/1/2007	10:35 PM	Jackson	State Route	'001100	1.27	2	'016100	0	0	Deer	Not A Collision With A Motor Vehicle	Gore	Dark-Not Lighted	Dry	S		Straight	
'55190743	8/20/2005	3:41 PM	Jackson	State Route	'001100	1.5		'	0	0	Deer	Not A Collision With A Motor Vehicle	On Roadway	Daylight	Dry	S		Straight	
'50260597	1/22/2005	3:00 AM	Jackson	State Route	'001100	1.63		'	0	0	Overtum	Not A Collision With A Motor Vehicle	Off Roadway	Dark-Not Lighted	Dry	W		Straight	
'60710072	2/10/2006	8:31 AM	Jackson	State Route	'001100	1.69		'	0	0	Ditch	Not A Collision With A Motor Vehicle	Off Roadway	Daylight	Dry	W		Entering/Leaving Driveway	
'60320156	1/6/2006	6:59 PM	Jackson	State Route	'001100	1.72		'	0	0	Deer	Not A Collision With A Motor Vehicle	On Roadway	Dark-Not Lighted	Dry	N		Straight	
'51390728	4/11/2005	4:27 PM	Jackson	State Route	'001100	1.73	2	'016200	0	0	Motor Vehicle in Motion	Angle	On Roadway	Daylight	Dry	W	S	Straight	Straight
'52980579	8/17/2005	6:33 PM	Jackson	State Route	'001100	1.73	2	'016200	0	0	Motor Vehicle in Motion	Angle	On Roadway	Daylight	Dry	W	N	Turning Left	Straight
'55190795	5/29/2005	2:24 PM	Jackson	State Route	'001100	1.73	2	'016200	0	0	Motor Vehicle in Motion	Rear End	On Roadway	Daylight	Dry	N	N	Straight	Stopped
'62010221	5/16/2006	2:00 PM	Jackson	State Route	'001100	1.73	2	'016200	0	0	Motor Vehicle in Motion	Angle	On Roadway	Daylight	Dry	W	W	Turning Left	Turning Left
'70270437	1/10/2007	7:52 PM	Jackson	State Route	'001100	1.73	2	'016200	0	0	Ditch	Not A Collision With A Motor Vehicle	Off Roadway	Dark-Lighted	Dry	E		Turning Left	
'75870005	11/23/2007	10:34 PM	Jackson	State Route	'001100	1.73	2	'016200	0	0	Animal	Not A Collision With A Motor Vehicle	On Roadway	Dark-Not Lighted	Dry	E		Straight	
'74940375	10/23/2007	12:55 PM	Jackson	State Route	'001100	1.73	2	'016200	0	0	Motor Vehicle in Motion	Rear End	On Roadway	Daylight	Dry	N	N	Straight	Straight
'80760209	2/19/2008	5:41 PM	Jackson	State Route	'001100	1.73	2	'016200	0	0	Ditch	Not A Collision With A Motor Vehicle	Off Roadway	Daylight	Dry	E		Straight	
'94490283	9/9/2009	11:48 AM	Jackson	State Route	'001100	1.73	2	'016200	2	0	Motor Vehicle in Motion	Angle	On Shoulder	Daylight	Dry	E	S	Straight	Straight
'84580359	10/4/2008	7:23 PM	Jackson	State Route	'001100	1.74		'	0	0	Other Non-Collision	Not A Collision With A Motor Vehicle	Off Roadway	Daylight	Dry	E		Straight	



# Bridge Inventory Data Listing



Parameters: Bridge Serial Num

**Structure ID:**157-0001-0

<b>Programming Data</b>		<b>Measurements:</b>		65 Inventory Rating Method:	0
201 Project No:	SAP 416-A REOP	*29ADT	003710 Year:3910	63 Operating Rating Method:	0
202 Plans Available:	1	109%Trucks:	11	66 Inventory Type:	2 Rating: 27
249 Prop Proj No:	000000000000000000000000	* 28 Lanes On:	02 Under:00	64 Operating Type:	2 Rating: 27
250 Approval Status:	0000	210 No. Tracks On:	00 Under:00	231 Calculated Loads:	
251 PI Number:	0000000	* 48 Max. Span Length:	0010	H-Modified:	00 0
252 Contract Date:	02/01/1901	* 49 Structure Length:	32	HS-Modified:	00 0
260 Seismic No:	00000	51 Br. Rwdy. Width:	0.00	Type 3:	00 0
75 Type Work:	00 0	52 Deck Width:	0.00	Type 3s2:	00 0
94 Bridge Imp. Cost:	\$0	* 47 Tot. Horiz. Cl:	35	Timber:	00 0
95 Roadway Imp. Cost:	0	50 Curb / Sidewalk Width:	0.00 / 0.00	Piggyback:	00 0
96 Total Imp Cost:	0	32 Approach Rdwy. Width:	028	261 H Inventory Rating:	15
76 Imp Length:	000000	*229 Shoulder Width:		262 H Operating Rating:	25
97 Imp Year:	0000	Rear Lt.:	2.20 Type:2 Rt:2.20	67 Structural Evaluation:	4
114 Future ADT:	005565 Year:3930	Fwd. Lt.:	2.20 Type:2 Rt:2.40	58 Deck Condition:	N
<b>Hydraulic Data</b>		Permanent Width:		59 Superstructure Condition:	N
215 Waterway Data:		Rear:	23.70 Type:2	* 227 Collision Damage:	0
High Water Elev.:	0000.0 Year:1900		23.20 Type:2	60A Substructure Condition:	N
Flood Elev.:	0000.0 Freq:00	Intersection Rear:	0 Fwd: 0	60B Scour Condition:	5
Avg Streambed Elev.:	0000.0	36 Safety Features Br. Rail:	N	60C Underwater Condition:	N
Drainage Area:	00000	Transition:	N	71 Waterway Adequacy:	9
Area of Opening:	000300	App. G. Rail:	N	61 Channel Protection Cond.:	5
113 Scour Critical:	8	App. Rail End:	N	68 Deck Geometry:	N
216 Water Depth:	06.2 Br.Height:09.8	53 Minimum Cl. Over:	99' 99"	69 UnderClr. Horz/Vert:	N
222 Slope Protection:	0	Under:		72 Appr. Alignment:	5
221 Slope Protection:	0 Fwd:0	*228 Minimum Vertical Cl:		62 Culvert:	4
219 Fender System:	0	Act. Odm Dir.:	99' 99"	<b>Posting Data</b>	
220 Dolphin:	0	Oppo. Dir.:	99' 99"	70 Bridge Posting Required:	5
223 Current Cover:	7	Posted Odm. Dir.:	00' 00"	41 Struct Open, Posted, CL:	A
Type:	1	Oppo. Dir.:	00' 00"	* 103 Temporary Structure:	0
No. Barrels:	3	55 Lateral Undercl. Rt:	N 0 0	232 Posted Loads:	
* Width:	10.00 Height:10.00	56 Lateral Undercl. Lt:	0.00	H-Modified:	00
* Length:	50 Apron:1	*10 Max Min Vert Cl:	99' 99" Dir:0	HS-Modified:	00
265 U/W Insp. Area:	0 Diver:ZZZ	39 Nav Vert Cl:	000 Horiz:0000	Type 3:	00
Location ID No.:	157-00011D-000.88N	116 Nav Vert Cl Closed:	000	Type 3s2:	00
		245 Deck Thickness Main:	0.00	Timber:	00
		Deck Thick Approach:	0.00	Piggyback:	00
		246 Overlay Thickness:	0.00	253 Notification Date:	02/01/1901
		212 Year Last Painted:	Sup:0000Sub:0000	258 Fed Notify Date:	2/1/1901 12:00:00AA

# Bridge Inventory Data Listing



Parameters: Bridge Serial Num

Structure ID:157-0001-0

Jackson

SUFF. RATING: 62.59

**Location & Geography**

Structure ID: 157-0001-0  
 200 Bridge Information: 07  
 \*6A Feature Int: MULBERRY RIVER TRIB  
 \*6B Critical Bridge: 0  
 \*7A Route No Carried: SR00011  
 \*7B Facility Carried: SR 11  
 9 Location: 6.3 MI SW OF JEFFERSON  
 2 Dot District: 1  
 207 Year Photo: 2012  
 \*91 Inspection Frequency: 24 Date: 08/08/2012  
 92A Fract Crit Insp Freq: 0 Date: 02/01/1901  
 92B Underwater Insp Freq: 0 Date: 02/01/1901  
 92C Other Spc. Insp Freq: 0 Date: 02/01/1901  
 \*4 Place Code: 00000  
 \*5 Inventory Route(O/U): 1  
 Type: 3  
 Designation: 1  
 Number: 00011  
 Direction: 0  
 \*16 Latitude: 34 03.8610 HMMS Prefix:SR  
 \*17 Longitude: 83 -39.7390 HMMS Suffix:00 MP:0.88  
 98 Border Bridge: 000%Shared:00  
 99 ID Number: 0000000000000000  
 \*100 STRAHNET: 0  
 12 Base Highway Network: 1  
 13A LRS Inventory Route: 1571001100  
 13B Sub Inventory Route: 0  
 101 parallel Structure: N  
 \*102 Direction of Traffic: 2  
 \*264 Road Inventory Mile Post: 000.87  
 \*208 Inspection Area: 1 Initials: EFP  
 Engineer's Initials: gmc  
 \* Location ID No: 157-00011D-000.88N

\*104 Highway System: 0  
 \*26 Functional Classification: 06  
 \*204 Federal Route Type: F No: 00522  
 105 Federal Lands Highway: 0  
 \*110 Truck Route: 0  
 2006 School Bus Route: 1  
 217 Benchmark Elevation: 0000.00  
 218 Datum: 0  
 \*19 Bypass Length: 04  
 \*20 Toll: 3  
 \*21 Maintenance: 01  
 \*22 Owner: 01  
 \*31 Design Load: 2  
 37 Historical Significance: 5  
 205 Congressional District: 10  
 27 Year Constructed: 1938  
 106 Year Reconstructed: 0000  
 33 Bridge Medium: 0  
 34 Skew: 00  
 35 Structure Flared: 0  
 38 Navigation Control: 0  
 213 Special Steel Design: 0  
 267 Type of Paint: 0  
 \*42 Type of Service On: 1  
 Type of Service Under: 5  
 214 Movable Bridge: 0  
 203 Type Bridge: Q  
 259 Pile Encasement: 3  
 \*43 Structure Type Main: 1 19  
 45 No.Spans Main: 003  
 44 Structure Type Appr: 0 00  
 46 No Spans Appr: 0000  
 226 Bridge Curve Horz: 0 Vert: 0  
 111 pier Protection: 0  
 107 Deck Structure Type: N  
 108 Wearing Structure Type: N  
 Membrane Type: N  
 Deck Protection: N

**Signs & Attachments**

225 Expansion Joint Type: 00  
 242 Deck Drains: 0  
 243 Parapet Location: 0  
 Height: 0  
 Width: 0  
 238 Curb Height: 0  
 Curb Material: 0  
 239 Handrail: 0 0  
 \*240 Medium Barrier Rail: 0  
 241 Bridge Median Height: 0  
 \* Bridge Median Width: 0  
 230 Guardrail Loc. Dir. Rear: 0  
 Fwrd: 0  
 Oppo. Dir. Rear: 0  
 Oppo. Fwrd: 0  
 244 Approach Slab: 0  
 224 Retaining Wall: 0  
 233 Posted Speed Limit: 55  
 236 Warning Sign: 0.00  
 234 Delineator: 0.00  
 235 Hazzard Boards: 0  
 237 Utilities Gas: 00  
 Water: 00  
 Electric: 00  
 Telephone: 00  
 Sewer: 00  
 247 Lighting Street: 0  
 Navigation: 0  
 Aerial: 0  
 \*248 County Continuity No.: 15

## CONCEPT TEAM MEETING (CTM) MINUTES

**PROJECT:** PI # 0011677, Jackson County  
SR 11 @ MULBERRY RIVER TRIBUTARY  
6.3 MI SW OF JEFFERSON

**LOCATION:** GDOT District 1 Office

**MEETING DATE:** December 17, 2014 at 9:00 AM

**ATTENDEES:** See attached sign-in sheet

Charles Robinson, the Project Manager called the meeting to order giving an overview of the project and asked all attendees to introduce themselves.

Charles Robinson then reviewed the project schedule. Charles confirmed that the project was on schedule to Let in January 2017.

Nicholas Mullins and Justin Lott led the review of the project's concept report and concept layouts including alternatives. The concept layouts included alternatives for an on-site detour as well as an off-site detour. The off-site detour was presented as the preferred alternative.

Ben Rabun asked if the GDOT Road User Costs spreadsheet had been completed for this project. Nick replied that it had not, but that it would be completed prior to the submission of the concept report for approval. Charles stated that the preferred concept layout would be determined after further review of the alternatives at the concept team meeting with the subject matter experts (SMEs), coordination with Jackson County and completion of the GDOT Road User costs spreadsheet. Justin Lott agreed.

Nick stated the cast in place option for the construction of the culvert was proposed based on some initial discussions with District 1 Construction Office. Ben Rabun stated that the precast culvert alternative may have benefits including but not limited to reduced construction time. Justin stated that both options will be carefully evaluated as the preliminary engineering design progresses.

Ben Rabun also inquired about the proposed trip times and detour route. The detour route included SR 319 which Brent Cook stated does not exist as shown on the detour layout. Justin stated that the detour routes and trip times will be revised accordingly.

**GEORGIA DEPARTMENT OF TRANSPORTATION  
MEETING / CONFERENCE RECORD OF ATTENDEES**

**PURPOSE:** P.I. No. 0011677 Concept Team Meeting

**LOCATION:** GDOT District 1 Office

**DATE:** 12/17/2013 **TIME:** 9:00 A.M.

**MODERATOR:** Charles A. Robinson

GDOT suffix: @dot.ga.gov

	NAME	ORGANIZATION	PHONE NO.	E-MAIL ADDRESS
1	Charles A. Robinson	GDOT- Office of Program Delivery	404-631-1439	chrobinson@dot.ga.gov
2	Kim Coley	GDOT- Planning	770-532-5530	kcoley@dot.ga.gov
3	Nathaniel O'Kelley	GDOT- Dist. Utilities	770-532-5510	noKelley@dot.ga.gov
4	Daniel Rock	GDOT- Design		drock@dot.ga.gov
5	Nick Muller	D1 Design	770-532-5112	nmuller@dot.ga.gov
6	Jeff Bridges	<del>GA</del> Jackson County	706-367-5288	jbridges@jacksoncountyga.gov
7	Lane Gortomollar	KEA Camp	678-904-8591	lgortomollar@keagroup.com
8	Linda E Taibol	Cumcarst	770-559-6541	Linda-Taibol@Cumcarst.com
9	Kathe Ahmed	GDOT-	404-631-1528	kahmed@dot.ga.gov
10	Steven Heng	GDOT- PM	404-631-1161	kh.heng@dot.ga.gov
11	Shane Gilles	District-Traffic Eng.	770-718-5041	shgilles@dot.ga.gov
12	Douglas Torres	GDOT-Lead Estimator	404-859-7463	dtorres@dot.ga.gov
13	Brandon Kirby	GDOT PM	678-3043-0816	bkirby@dot.ga.gov
14	JASON DYKES	GDOT- ADCE	770-718-5023	JDYKES@DOT.GA.GOV
15	Robert Cook	GDOT- DPE	770-532-5522	brock@dot.ga.gov
16	Tammy Crochet	Mabee Partners	770-933-6400	tcrochet@mabeepartners.com
17	Bret Anderson	GDOT - Gate Flow	770-718-5042	banderson@dot.ga.gov
18	Ben Rabun	GDOT- Bridge Design	404-631-1985	brabun@dot.ga.gov

\* teleconference

**Project:** PI 0011677, Jackson County  
SR 11 @ Mulberry River Tributary  
6.3 Miles southwest of Jefferson

**Date:** February 11, 2014 at 10:05 AM

**Subject:** Phone Conversation with Jackson County and GDOT  
Discussion of Off-Site Detour

**Attendees:** Kevin Poe- Jackson County- County Manager  
Justin Lott- GDOT- District Design Engineer

- Justin Lott stated that GDOT's preferred alternate would be to construct the project using an off-site detour. The Jackson County Roads Superintendent attended the Concept Team Meeting and did not seem to have a problem using an off-site detour.
- Kevin Poe asked what the off-site detour route would be. Justin said it would consist of using SR 211, SR 82, and SR 11 Connector.
- Justin indicated that the detour route would be limited to only state routes, however, local residents may choose to utilize county roads they are familiar with.
- Kevin said that he was not sure that the county commissioners would be in favor of the off-site detour and he would check with them.
- Kevin asked Justin what the approximate detour time would be and Justin said it would likely be between 2-6 months. The exact timeframe would be worked out during the preliminary design process.
- Kevin said his main concern would be trucks using the county roads rather than the official detour route.
- Justin indicated the other project alternate that was being considered was an on-site detour that would keep one lane of traffic open using a temporary traffic signal. The temporary traffic signal would allow each direction of travel to utilize the one lane open during construction of the project.
- Kevin checked with the Commissioners whose area is affected by the project and they were not in favor of the off-site detour.
- Kevin did say the Commissioners would support using the on-site detour keeping one lane of traffic open with a temporary traffic signal.
- Justin told Kevin the concept report would be revised so the on-site detour would be the selected alternate.

## Houppermans, Colin

---

**From:** Bowman, Glenn  
**Sent:** Thursday, May 22, 2014 8:07 AM  
**To:** Lott, Justin  
**Cc:** Houppermans, Colin; Robinson, Charles A.; Cook, Brent; Simpson, Jim; Peters, Dave; Phillips, Kim  
**Subject:** RE: 0011677, Jackson Concept Report

**Follow Up Flag:** Follow up  
**Flag Status:** Flagged

I discussed the design exception with the Chief and we agreed that using the existing (30 mph) profile would be acceptable for this culvert replacement project as long as there is no discernable accident history due to this feature. Please look into this and if there is no history then move forward with it, otherwise we'll have to reassess. PE estimate is ok too so just keep holding the line to keep costs as low as possible. Thanks for your patience!

Glenn Bowman, P.E.  
Director of Engineering  
Georgia Department of Transportation  
600 West Peachtree Street, NW - 25<sup>th</sup> Floor  
Atlanta, Georgia 30308  
Office: 404-631-1519 Mobile: 404-326-5871

---

**From:** Bowman, Glenn  
**Sent:** Tuesday, May 20, 2014 12:08 PM  
**To:** Lott, Justin  
**Cc:** Houppermans, Colin; Robinson, Charles A.; Cook, Brent; Simpson, Jim; Peters, Dave; Phillips, Kim  
**Subject:** RE: 0011677, Jackson Concept Report

Thanks, and you're right on #1. I will make sure the Chief is on board as he just might overrule me and sign an exception for 30 mph. My meeting with him this afternoon may get cancelled but I will surely get an answer by tomorrow and let you know.

Glenn Bowman, P.E.  
Director of Engineering  
Georgia Department of Transportation  
600 West Peachtree Street, NW - 25<sup>th</sup> Floor  
Atlanta, Georgia 30308  
Office: 404-631-1519 Mobile: 404-326-5871

---

**From:** Lott, Justin  
**Sent:** Tuesday, May 20, 2014 11:15 AM  
**To:** Bowman, Glenn  
**Cc:** Houppermans, Colin; Robinson, Charles A.; Cook, Brent; Simpson, Jim; Peters, Dave; Phillips, Kim  
**Subject:** RE: 0011677, Jackson Concept Report

Glenn,

I have a few other things to run by you mainly in regards to the comments below.

1. I am not comfortable with recommending a design exception for the 30 mph sag that hugs the existing so please use the single 850' VC (a 45 mph design that will also be a design exception.)

- We have developed a design that has a 45 mph design sag vertical curve in it (see attached). If we put in a 45 mph vertical curve our cost estimate is approximately what was submitted in the previous concept report that got rejected. Colin prepared a spreadsheet to outline the previous rejected amount, an estimate using the existing profile, and an alternate to raise the profile to meet a 45 mph design speed (see attached). The higher cost is mainly due to more earthwork, more full depth pavement, a longer culvert, and slightly longer project limits. Do you still want us to go with the 45 mph vertical curve? If so, we will revise the concept report and resubmit. I just wanted to make sure it wouldn't be rejected again due to construction cost.
- 2. Shouldn't the PE costs be lower? You won't need to do extensive staging, fewer plan sheets, etc. The PE estimate should be what we've already spent plus what it will take to complete the project from now, not what the programmed amount is.
  - The programmed amount of PE funds on this project is approximately \$421,000 with \$221,000 in contract funds for survey and environmental work and \$200,000 in funds for in-house. In regards to the in-house funds, we have already spent approximately \$82,000 in in-house PE funds. This is more than I would expect but the GDOT survey crew has had to go out and pick up additional data because the consultant survey crew had angered a property owner. Also, there were some points that were not within tolerance that may have required more field work. I have attached a man-hour estimate that estimates the remaining design work at approximately \$75,000. I did not adjust the hourly rates but they appear to be low in comparison to the recent job worth study. According to the values in District 1, I would expect the DEGM hourly rate to be about \$6 higher and the LDE rate to be about \$5 higher. The design engineer rate is pretty close. Assuming, the hourly rates don't need adjustment this brings the new PE estimate to \$157,000. That does not include any hours that are charged to it from Program Delivery, Environmental, Engineering Services, Design Policy & Support, etc.
- 3. Please put a double asterisk beside the CST estimate with a note below: "\*\*Construction estimate is based on a cast in place alternate. However, project will be investigated for precast alternate design/bidding which may reduce costs further."
  - Will do.

Please let me know if you have any other questions.

Thanks,

Justin Lott, P.E.  
District Design Engineer  
Phone: 770-718-5005  
GDOT- District 1 Design  
2505 Athens Highway, SE  
Gainesville, GA 30507  
[jlott@dot.ga.gov](mailto:jlott@dot.ga.gov)



[Georgia DOT - NE on Twitter](#)



[Georgia DOT - Northeast Facebook](#)

---

**From:** Bowman, Glenn  
**Sent:** Friday, May 09, 2014 5:49 PM  
**To:** Lott, Justin  
**Cc:** Houppermans, Colin; Robinson, Charles A.; Cook, Brent; Simpson, Jim; Peters, Dave  
**Subject:** RE: 0011677, Jackson Concept Report

Sorry guys, this got by me. I think we can make a good argument now that the project is minimized. A few other things:

1. I am not comfortable with recommending a design exception for the 30 mph sag that hugs the existing so please use the single 850' VC (a 45 mph design that will also be a design exception.)
2. Shouldn't the PE costs be lower? You won't need to do extensive staging, fewer plan sheets, etc. The PE estimate should be what we've already spent plus what it will take to complete the project from now, not what the programmed amount is.
3. Please put a double asterisk beside the CST estimate with a note below: "\*\*\*Construction estimate is based on a cast in place alternate. However, project will be investigated for precast alternate design/bidding which may reduce costs further."

Glenn Bowman, P.E.  
Director of Engineering  
Georgia Department of Transportation  
600 West Peachtree Street, NW - 25<sup>th</sup> Floor  
Atlanta, Georgia 30308  
Office: 404-631-1519 Mobile: 404-326-5871

---

**From:** Lott, Justin  
**Sent:** Wednesday, April 30, 2014 12:15 PM  
**To:** Bowman, Glenn  
**Cc:** Houppermans, Colin; Robinson, Charles A.; Cook, Brent; Simpson, Jim; Peters, Dave  
**Subject:** RE: 0011677, Jackson Concept Report

Glenn,

We had another discussion with Jackson County and they indicated that they would be agreeable to an off-site detour if it helped us on the construction cost and kept the project moving. We also talked to the District Construction Office and they think the work could be accomplished by detouring 2-3 months. Based on GA standard 2530P, the maximum fill height would be 10 feet above a precast 10'x10' multi barrel culvert. We would be pushing this threshold as our design would require approximately 10-12 feet of cover. District Construction also prefers the cast-in-place option.

Colin has reduced the project limits, reduced the shoulder width to the AASHTO minimum (8'), and recalculated the cost estimates based on those changes. Please see the attached cost estimate comparison that shows the reductions. This amount is still higher than the STIP amount but I don't know what other actions that can be taken to reduce the amount. Could you check and see if these values would be acceptable prior to us resubmitting the concept report?

Also, a design exception for vertical curves would be needed in order to keep the profile as close to existing as possible (see attached). I'm assuming it would not be a problem to get these two vertical curve exceptions approved so we can keep project cost down. Is that correct?

Please let us know if you have any questions.

Thanks,

Justin Lott, P.E.  
District Design Engineer  
Phone: 770-718-5005

GDOT- District 1 Design  
2505 Athens Highway, SE  
Gainesville, GA 30507  
[jlott@dot.ga.gov](mailto:jlott@dot.ga.gov)



[Georgia DOT - NE on Twitter](#)



[Georgia DOT - Northeast Facebook](#)

---

**From:** Bowman, Glenn  
**Sent:** Friday, April 25, 2014 3:37 PM  
**To:** Lott, Justin  
**Subject:** RE: 0011677, Jackson Concept Report

Emphasize that we are proposing a very short closure at 3 months or less. Talk to construction. Seems to me we could dig out the old one in a week, install a new precast one in two, and fill and pave in a couple more.

Glenn Bowman, P.E.  
Director of Engineering  
Georgia Department of Transportation  
600 West Peachtree Street, NW - 25<sup>th</sup> Floor  
Atlanta, Georgia 30308  
Office: 404-631-1519 Mobile: 404-326-5871

---

**From:** Lott, Justin  
**Sent:** Friday, April 25, 2014 10:59 AM  
**To:** Bowman, Glenn  
**Subject:** RE: 0011677, Jackson Concept Report

Thanks for the heads up Glenn!! We are currently reviewing what options we have available. Early indication is saying that the off-site detour would be the best cost savings measure. I will coordinate with Jackson County again to see if they will reconsider their opinion.

Thanks,

Justin Lott, P.E.  
District Design Engineer  
Phone: 770-718-5005  
GDOT- District 1 Design  
2505 Athens Highway, SE  
Gainesville, GA 30507  
[jlott@dot.ga.gov](mailto:jlott@dot.ga.gov)



[Georgia DOT - NE on Twitter](#)



[Georgia DOT - Northeast Facebook](#)

---

**From:** Bowman, Glenn  
**Sent:** Wednesday, April 23, 2014 8:24 AM  
**To:** Lott, Justin  
**Cc:** Robinson, Charles A.; Cook, Brent; Simpson, Jim; Peters, Dave  
**Subject:** 0011677, Jackson Concept Report

Justin,

I wanted to give you a heads up that the Chief has rejected the subject Concept Report in its current form. His main concern is the high project cost for a culvert replacement. He questioned why PE is 50% of construction costs and noted the total estimate is now 55% over the STIP estimate. We must bring these down.

Can't we shorten the southern project limit considerably? Should be able to come out of existing curve smoothly to the detour alignment without having to rebuild the whole curve. Or could we simply tell the locals the cost for staging the onsite detour is simply too high and we'll expedite construction, say three month closure during the summer months? Wouldn't a precast alternative help drive down construction time? Just some ideas. We are behind the baseline already so the changes must be expedited.

I am routing the report back through Design Policy.

Glenn Bowman, P.E.  
Director of Engineering  
Georgia Department of Transportation  
600 West Peachtree Street, NW - 25<sup>th</sup> Floor  
Atlanta, Georgia 30308  
Office: 404-631-1519 Mobile: 404-326-5871

---

Georgia DOT commits \$7 million per year to an Off-System Safety Improvement Program designed to reduce fatalities and serious injuries on rural roads owned and maintained by local governments throughout Georgia. Thus far in FY2014, GDOT has administered approximately \$6.5 million of federal funds for local assistance in 78 counties. Visit us at <http://www.dot.ga.gov> (Local Government link) or follow us on <http://www.facebook.com/GeorgiaDOT> and <http://twitter.com/gadepoftans>.