# DEPARTMENT OF TRANSPORTATION STATE OF GEORGIA

# OFFICE OF DESIGN POLICY & SUPPORT INTERDEPARTMENTAL CORRESPONDENCE

FILE P.I. # 0012826

**OFFICE** Design Policy & Support

DeKalb County

GDOT District 7 - Metro Atlanta

Signals: SR 155 at 4 locations in

**DATE** 2/5/2016

DeKalb County

**FROM** 

for Brent Story, State Design Policy Engineer

TO SEE DISTRIBUTION

SUBJECT APPROVED CONCEPT REPORT

Attached is the approved Concept Report for the above subject project.

Attachment

#### **DISTRIBUTION:**

Hiral Patel, Director of Engineering

Joe Carpenter, Director of P3/Program Delivery-

Genetha Rice-Singleton, Assistant Director of P3/Program Delivery

Albert Shelby, State Program Delivery Engineer

Darryl VanMeter, State Innovative Delivery Engineer

Bobby Hilliard, Program Control Administrator

Cindy VanDyke, State Transportation Planning Administrator

Eric Duff, State Environmental Administrator

Bill DuVall, State Bridge Engineer

Andrew Heath, State Traffic Engineer

Angela Robinson, Financial Management Administrator

Lisa Myers, State Project Review Engineer

Charles "Chuck" Hasty, State Materials Engineer

Lee Upkins, State Utilities Engineer

Richard Cobb, Statewide Location Bureau Chief

Ed David Adams, State Safety Program Manager

Kathy Zahul, District Engineer

Scott Lee, District Preconstruction Engineer

Nicholas Fields, District Utilities Engineer

Xavier James, Project Manager

BOARD MEMBER - 4th, 5th, 6th Congressional District


### DEPARTMENT OF TRANSPORTATION STATE OF GEORGIA LIMITED SCOPE PROJECT CONCEPT REPORT

Project Type:	Reconstruction/ Rehabilitation	P.I. Number:	0012826
GDOT District:	7	County:	DeKalb
Federal Route Number:	23	State Route Number:	
	Project Number:	0.74	
Traffic Signal Upgrades for	3 Signals and communicatio	ns for 4 locations along SR	155 in Dekalb County.
Submitted for approval:	1.		17/10/10
Douglas Tilt, P.E. APCADIS U	J.S., Inc.		Date 73
albert Sh	elly		12/15/15
State Program Delivery Engir	C.1.5   KUN		Date
GDOT Project Mariager			12/9/15 Date
	TII		
Recommendation for appr	roval:		1116/2016
State Environmental Administ	irator		Date
KEW WERH	D Mark Su		12/22/2019
State Traffic Engineer			Date
	oject is consistent with the M Transportation Plan (LRTP).		sportation Plan
Rural Area: This pro	ject is consistent with the go	eals outlined in the Statewid	e Transportation Plan m (STIP).
Contlya &	Voucke		1-4-16
State Transportation Planning	ng Administrator		Date
Approval:			
Concur: GDOT Directo	or of Engineering		02   21 - 16 Date
Approve:	920904B	ANLO	2.3.16
GDOT Chief I	Engineer		Date

\* RECOMMENDATION ON FILE:

P.I. Number: 0012826

### **PROJECT LOCATION**



Limited Scope Concept Report – Page 3

County: DeKalb

#### **PLANNING & BACKGROUND DATA**

Project Justification Statement: P.I. Number0012826

The following intersections located in DeKalb County have been identified by the Office of Traffic Operations as high priority for minor intersection improvements. The proposed project is to be included in the Region wide Signal Upgrade Lump Sum Program.

P.I. Number: 0012826

- SR 155/US 23 (Clairmont Rd) @ Briarcliff Rd (Signal Upgrade)
- SR 155/US 23 (Clairmont Rd) @ I-85 NB (Signal Upgrade)
- SR 155/US 23 (Clairmont Rd) @ I-85 SB (Signal Upgrade)
- SR 155/US 23 (Clairmont Rd) @ Sam's Club (Communication Only)

The project will upgrade equipment, accommodate pedestrians, and bring intersections to ADA standards. The District has given the following reasons for these intersections to be upgraded: pedestrian accommodations, ADA compliance, replace old conductor cable, install 332 cabinet w/2070 controller, replace support poles (mast arms), address utility issues, and upgrade to fiber optic communications.

#### **Existing conditions:**

#### 1. SR 155/US 23 (Clairmont Rd) @ Briarcliff Rd

- SR 155/US 23 (Clairmont Rd) Mainline Design Features:
  - SR 155 is an undivided roadway with 4 lanes, curb and gutter, sidewalk, and left turn lanes.
- Briarcliff Rd Side Road Features:
  - This roadway has 2 lanes, left and right turn lanes, sidewalk, curb and gutter.

#### 2. SR 155/US 23 (Clairmont Rd) @ I-85 NB

- SR 155/US 23 (Clairmont Rd) Mainline Design Features:
  - SR 155 is a divided roadway with 3 through lanes and a right turn lane with a concrete island northbound, 2 through lanes and two left turn lanes southbound, curb and gutter, and sidewalk.
- I-85 NB Side Road Features:
  - o This roadway has 2 through lanes, a left turn lane, a right turn lane with a concrete median eastbound, curb and gutter, and no westbound traffic.

#### 3. SR 155/US 23 (Clairmont Rd) @ I-85 SB

- SR 155/US 23 (Clairmont Rd) Mainline Design Features:
  - SR 155 is a divided roadway with 4 lanes, curb and gutter, a right turn lane southbound, two left turn lanes northbound, sidewalk, and curb and gutter.
- I-85 SB Side Road Features:
  - This roadway has 2 through lanes, a u-turn lane to I-85 S, a left turn lane, a right turn lane with a concrete median westbound, curb and gutter, and no eastbound traffic.

#### 4. SR 155/US 23 (Clairmont Rd) @ Sam's Club

- SR 155/US 23 (Clairmont Rd) Mainline Design Features:
  - SR 155 is an undivided roadway with 4 lanes, curb and gutter, a left turn lane southbound, left and right turn lanes northbound, curb and gutter, and 5 foot sidewalks.
- Sam's Club Side Road Features:
  - The roadway has one through/left turn lane and one right turn lane westbound, and easrbound there is a driveway from a gas station and apartment complex with one through lane.

#### Other projects in the area:

PI0002903: SR 155 from I-85 to SR 13 - Phase I

Addition of 4' sidewalks along both sides of the road from N Druid Hills Rd to SR 13. Crosswalks will be included as appropriate.

Limited Scope Concept Report – Page 4 County: DeKalb	P.I. Nur	nber: 0012826	
Description of the proposed project: The proposed project is located along SR 155 in approximate length of the project is 0.33 miles a vehicular signals, countdown pedestrian signals cable will also be added along the length of the	and will consist of traffic signalizat , ADA curb ramps, and crosswalk	ion upgrades, inc	luding LED
MPO: Atlanta Regional Commission (ARC)		TIP #: DK-423	
TIA Regional Commission: Not a TIA Project MPO Name Congressional District(s): 4, 5, 6			
Federal Oversight: ⊠Exempt □State	e Funded □Other		
Projected Traffic: N/A Current Year (20WW): N/A Open Year (2		(20YY): <u>N/A</u>	
Traffic Projections Performed by: N/A			
Functional Classification (Mainline): Urban F	Principal Arterial		
Complete Streets - Bicycle, Pedestrian, and/o Warrants met: □None □Bicycle	or Transit Standards Warrants:	ALESA)	
Pavement Evaluation and Recommendations Preliminary Pavement Evaluation Summary Re Preliminary Pavement Type Selection Report F Feasible Pavement Alternatives:	eport Required?⊠No Required?⊠No	□Yes □Yes A & PCC	
DESIGN AND STRUCTURAL Description of Proposed Project: Major Structures: N/A			
Mainline Design Features: SR 155/US 23			
Feature	Existing	Standard*	Proposed
Typical Section	F 0		
- Number of Lanes	5 - 8		
- Lane Width(s)	12 ft.		
- Median Width & Type	12 ft. Center Turn Lane and Variable Width Raised Median		
- Sidewalks	Υ		
- Auxiliary Lanes	Left & Right Turn Lanes		
Posted Speed	40 mph		
*According to current GDOT design policy if app	12 Contain Con	t 2 ° 0	

Major Interchanges/Intersections:
I-85 & SR 155/US 23 Clairmont Rd.

Lighting required:
□ No
□ Yes

Transportation Management Plan [TMP] Required:
□ No
□ Yes

If Yes:
Project classified as:
□ Non-Significant
□ Significant

TMP Components Anticipated:
□ TO
□ PI

County: DeKalb					
Will Context Sensitive Design Exceptions to Design Variances to G	FHWA/AASHTO	O controlling cri	teria anticipate	⊠ No <b>d:</b> None	☐ Yes
UTILITY AND PF Temporary State Rout	_	⊠ No	□ Yes	☐ Undetermine	d
Railroad Involvement:	None				
Utility Involvements:  AT&T - Communication Atlanta Gas Light - Gas Comcast - Communcat Dekalb County - Traffic Dekalb County - Water Georgia Power - Electri Charter - Communicatio Verizon - Communicatio Dukenet - Communicati American Traffic Solutio Qwest - Communication TW Telecomm - Communication Zayo Fiber Solutions - Georgia	ion & Safety & Sewer ical on ion ion ions n				
SUE Required:	⊠ No	□Yes			
Public Interest Determ	ination Policy	and Procedure	recommended?	<sup>P</sup> ⊠ No	□ Yes
Right-of-Way: Required Right-of-Way	Existing width: anticipated:	<u>80 − 140</u> ft.	Propos ⊠ Yes	ed width: $80 - 1$ Undetermine	
Easements anticipated:	⊠ None	☐ Temporary	☐ Permanent	☐ Utility	□ Other
Di		tal number of im ticipated: 0 Total I		0	
ENVIRONMENT Anticipated Environme GEPA:			:		
MS4 Compliance – Is t	he project loca	ited in an MS4 a	rea? □ No	⊠ Yes	
Environmental Permits	s, Variances, C	ommitments, ar	nd Coordination	n anticipated:	
	cated in an Ozo	5 Non-attainmer ne Non-attainme ⁄sis: □ Req	nt area? □ No	⊠ Yes ⊠ Yes ot Required	□ TBD
This project is exempt a from a CO hotspot.	and does not ad	d capacity or cha	ange roadway co	onditions; therefo	re, it is excluded

P.I. Number: 0012826

Limited Scope Concept Report – Page 5

Limited Scope Concept Report – Page 6

County: DeKalb

P.I. Number: 0012826

#### **NEPA/GEPA Comments & Information:**

#### Ecology:

- A Section 404 Permit would be required if USACE-Jurisdictional waters are impacted by the proposed project. Mitigation credits would be required to be purchased if the impacts exceeded 100 linear feet for streams or 0.1 acre for wetlands. Design will avoid any impacts.
- A stream buffer variance would be required for any impacts within-25-foot of top of bank at USACE-jurisdictional streams or state buffered waters. Stream buffer credits may be required based on the type of impact. Design will avoid any impacts.
- A National Pollutant Discharge Elimination System (NPDES) permit would be required for greater than 1.0 acre of disturbance for the proposed project. Design will avoid any impacts.

#### **Community Resources or Institutions:**

Church – West of SR 155 on Briarcliff Rd. Design will avoid any impacts.

#### Potential Underground Storage Tanks (USTs) and Hazardous Waste Sites:

- QuikTrip, Chevron, Auto Shop, Express Oil Change & Tune Up Clinic Intersection 1 (SR 155 @ Briarcliff Rd)
- BP Station Intersections 3 and 4 (SR 155 @ I-85 SR and SR 155 @ Sam's Club)

**Air Quality:** Project is located in a non-attainment area for PM 2.5 and Ozone. CO hotspot analysis not required. Project exempt from PM2.5

Noise: Type III noise assessment is anticipated.

#### COORDINATION, ACTIVITIES, RESPONSIBILITIES, AND COSTS

Project Meetings: Field Visit Kickoff Meeting September 2, 2015. Minutes Attached.

Project Activity	Party Responsible for Performing Task(s)
Concept Development	ARCADIS-US INC.
Design	ARCADIS-US INC.
Right-of-Way Acquisition	GDOT
Utility Coordination (Preconstruction)	Utility Owners Coot 1
Utility Relocation (Construction)	Utility Owners
Letting to Contract	GDOT
Construction Supervision	GDOT
Providing Material Pits	NA a
Providing Detours	NA
Environmental Studies, Documents, & Permits	GDOT
Environmental Mitigation	GDOT
Construction Inspection & Materials Testing	GDOT

#### Other coordination to date:

**Project Cost Estimate and Funding Responsibilities:** Add additional rows as necessary; Attach current cost estimates to report.

	Breakdown of PE	ROW	Reimbursable Utility	CST*	Environmental Mitigation	Total Cost
Funded By	GDOT	GDOT	GDOT	GDOT	N/A	
\$ Amount	200,000	114,000.00	135,000.00	510,778.48		959,778.48
Date of Estimate	10/19/2015	12/07/2015	11/9/2015	10/19/2015	- 1	

Limited Scope Concept Report – Page 7 P.I. Number: 0012826

County: DeKalb

\*CST Cost includes: Construction, Engineering and Inspection, Contingencies and Liquid AC Cost Adjustment.

#### **Comments/Additional Information:**

### LIST OF ATTACHMENTS/SUPPORTING DATA

List and attach as appropriate to project. Please see PDP Appendix A for a more complete list of potential attachment.

- 1. Field Visit Kick-off Meeting Minutes
- 2. Construction Cost Estimates
- 3. Revisions to Programmed Costs
- 4. Preliminary Utilility Cost Estimate
- 5. Preliminary ROW Estimate



#### **MEETING MINUTES**

ARCADIS
2410 Paces Ferry Road
Suite 400
Atlanta
Georgia 30339
Tel 770.431.8666
Fax 770.435.2666

PI Numbers:

Subject

Field Visit Kick-Off Meeting Minutes TO#11 Traffic Signal Upgrade Project DeKalb County

PI0012826

Department:

Georgia Department of Transportation

Place/Date of Meeting: SR 155 @ Briarcliff Rd

Chuck Fisher, ARCADIS

September 2, 2015 10:00 AM to 12:00 PM

Minutes by:

Chuck Fisher

Issue Date:

September 9, 2015

Participants

Xavier James, GDOT- Office of Program Delivery Edlin Regis, GDOT D7 Signals
Nick Fields, GDOT D7 Utilities
Justin Hatch, GDOT-Traffic Operations
Guy Olmstead, Dekalb County
Michael Margud, GDOT- OES
Kay Abikoye, GDOT- OES
Keisha Jackson, GDOT-OES
Jim Secrist, SEI
Heather Perrin, Edwards Pittman
Kristen Phillips, Wolverton
Mike Holt, Parsons Brinckerhoff
Doug Tilt, ARCADIS
Vamshi Mudumba, ARCADIS

Copies:

**Participants** 

#### **ARCADIS**

#### **General Comments:**

- Use loop detection only
- Existing fiber runs length of project aerially. Proposed fiber connecting the 4 intersections including the Sam's Club intersection will be a 72 SM Fiber
- Provide new signing and marking at the 3 intersections with limits extending till the detector loops

#### **Intersection Comments:**

#### #1 SR 155/ US 23 @ Briarcliff Rd

- Intersection has been recently milled & striped
- Relocate the damaged utility pole at the NE corner of the intersection
- Mast arms will be considered at the intersection, if feasible. Provide new signal heads with FYA.
- Upgrade the intersection with new pedestrian poles per ADA compliance
- Provide a separate power meter for the CCTV camera
- Identify the possibility for having a separate pole for the overhead signs along SB Clairmont Rd
  (125' North of the intersection) rather than having a joint use pole with utilities. If separate pole is
  used, existing signs to be relocated.

#### #2 SR 155/ US 23 278 @ I-85 NB Ramp

- Need to upgrade guardrail (T-beam) at northwest corner if pole is located on island.
- Address safety concerns for crosswalk at south east of intersection by relocating crosswalk and ramp south. Also, replace curb and remove sidewalk north of new ramp location.
- Upgrade the intersection with span wire configuration
- Provide new signal heads with FYA and update the signal head alignment for the split phasing for the EB traffic
- At SW corner of the intersection, modify island and right through lane to allow easier right turns from the 2<sup>nd</sup> lane.
- Visible rock at SW corner. Alternative foundation types may need to be considered for strain pole installation
- Upgrade the intersection with new pedestrian facilities per ADA compliance

#### #3 SR 155/ US 23 278 @ I-85 SB Ramp

- In order to widen island for pedestrian access, restripe to reduce the width of existing westbound through lane to approximately 12'.
- Consider providing a signal for the westbound right turning vehicles at the intersection
- Provide new signal heads with FYA and update the signal head alignment for the split phasing for the WB traffic
- Upgrade the intersection with span wire configuration
- Relocate the existing CCTV camera on the SE corner to new strain pole.
- Upgrade the intersection with new pedestrian facilities per ADA compliance

### **ARCADIS**

#### #4 SR 155/ US 23 278 @ Sam's Club

- Intersection has been recently upgraded. No Signal upgrades are needed
- Splice the new 72 SM fiber to the existing fiber cable in the existing pull box on the NE corner, near the signal cabinet.
- Retain the existing Switch in the cabinet and provide new Gbics

# DEPARTMENT OF TRANSPORTATION STATE OF GEORGIA

### INTERDEPARTMENT CORRESPONDENCE

FILE	P.I. No.	00 <b>12826</b>	OFFICE	Program Delivery
PROJE	CT DESCR	IPTION		
SR 155	@4 LOCS IN	DEKALB	DATE	December 8, 2015
			DATE	December 8, 2013
		A make	Un Testit for	
From:	Albert V. S	Shelby, III, Program Delivery Engineer	11, 400	
To:	Lisa L. My	ers, State Project Review Engineer		
Subject	: REVISION	NS TO PROGRAMMED COSTS		
			MGMT LET DATE	5/15/2018
PROJEC	CT MANAG	ER Xavier James	MGMT ROW DATE	5/15/2017
PROGR	RAMMED C	COSTS (TPro W/OUT INFLATION)	LAST	ESTIMATE UPDATE
CONST	RUCTION	\$ 1,146,600.00	DATE	8/8/2014
RIGHT	OF WAY	\$ 400,000.00	DATE	8/8/2014
UTILIT	IES	\$	DATE	
REVISI	ED COST E	<u>STIMATES</u>		
CONST	RUCTION*	\$ 510,778.48		
RIGHT	OF WAY	\$ 114,000.00		
UTILIT	IES	\$ 135,000.00		
*Cost (	Contains	5 % Contingency		
		OST INCREASE AND CONTINGEN		
8-3A	-	al (Reconstruction/Rehabilitation) projectly in the concept phase.	ct and is at low risk. The co	ontingency chosen is 5%
Jocause	it is current	i iii oonoopt piidoo.		

# **CONTINGENCY SUMMARY**

A. CONSTRUCTION COST ESTIMATE:	\$	463,291.14	Base Estimate From CES	
B. ENGINEERING AND INSPECTION (E & I):	\$	23,164.56	Base Estimate (A) x	5 %
c. CONTINGENCY:	\$	24,322.78	Base Estimate (A) + E & I (B) x  See % Table in "Risk Based Cost  Estimation" Memo	5 %
D. TOTAL LIQUID AC ADJUSTMENT:	\$		Total From Liquid AC Spread	Isheet
E. CONSTRUCTION TOTAL:	\$	510,778.48	(A + B + C + D = E)	
REI	MBURS	SABLE UTI	LTY COSTS	
UTILITY OWNER			REIMBURSABLE COST	
Georgia Power Company		\$		135,000.00
	317 Aug. 2			
1000				-11 12 112
TOTAL		\$	**************************************	135,000.00
ATTACHMENTS:				

Page 2

CST Estimate

Utility Cost Estimate ROW Cost Estimate

Preconstruction Status Report

DATE : 10/19/2015

PAGE : 1

#### JOB DETAIL ESTIMATE

JOB NUMBER : PI0012826 SPEC YEAR: 13

DESCRIPTION: TRAFFIC SIGNAL UPGRADE SR 155

#### ITEMS FOR JOB PI0012826

LINE	ITEM	ALT	UNITS	DESCRIPTION	QUANTITY	PRICE	AMOUNT
0005	150-1000		LS	TRAFFIC CONTROL - TRAFFIC CONTROL	1.000	60000.00	60000.00
0008	165-0030		LF	MAINT OF TEMP SILT FENCE, TP C	500.000	0.98	490.33
0009	171-0030		LF	TEMPORARY SILT FENCE, TYPE C	500.000	3.25	1626.98
0010	163-0550		EA	CONS & REM INLET SEDIMENT TRAP	6.000	143.46	860.80
0015	441-0106		SY	CONC SIDEWALK, 6 IN	250.000	34.15	8537.80
0020	441-6012		LF	CONC CURB & GUTTER/ 6X24TP2	150.000	12.94	1941.35
0022	441-0748		SY	CONC MEDIAN, 6 IN	20.000	55.92	1118.49
0023	610-1055		LF	REM GUARDRAIL	150.000	8.32	1248.04
0024	610-1067		EA	REM GUARDRAIL ANCH, TP 2	1.000	500.00	500.00
0025	610-2805		SY	REM CONC MEDIAN PAVING	80.000	50.00	4000.00
0030	610-2815		SY	REM CONC SIDEWALK	40.000	50.00	2000.00
	636-1033		SF	HWY SIGNS. TP1MAT.REFL SH TP 9	190.000	19.47	3700.75
	636-2070		LF	GALV STEEL POSTS. TP 7	26.000	12.33	320.83
	639-3004		EA	STEEL STRAIN POLE. TP IV	10.000	12779.36	127793.62
	641-1100		LF	GUARDRAIL. TP T	150.000	54.12	8118.50
	647-1000		LS LF EA SY LF EA SY LF EA SY LF EA SY SY LF LF LF LF LF LS	TRAFFIC CONTROL - TRAFFIC CONTROL MAINT OF TEMP SILT FENCE, TP C TEMPORARY SILT FENCE, TYPE C CONS & REM INLET SEDIMENT TRAP CONC SIDEWALK, 6 IN CONC CURB & GUTTER/ 6X24TP2 CONC MEDIAN, 6 IN REM GUARDRAIL REM GUARDRAIL ANCH, TP 2 REM CONC MEDIAN PAVING REM CONC SIDEWALK HWY SIGNS, TP1MAT, REFL SH TP 9 GALV STEEL POSTS, TP 7 STEEL STRAIN POLE, TP IV GUARDRAIL, TP T TRAF SIGNAL INSTALLATION NO - TRAFFIC SIGNAL INSTALLATION #1	1.000	60000.00 0.98 3.25 143.46 34.15 12.94 55.92 8.32 500.00 50.00 50.00 19.47 12.33 12779.36 54.12 60000.00	60000.00
0060	647-1000		LS	TRAF SIGNAL INSTALLATION NO - TRAFFIC SIGNAL INSTALLATION #2	1.000		
0065	647-1000		LS	TRAF SIGNAL INSTALLATION NO - TRAFFIC	1.000	60000.00	
0070	647-2170		EΛ	DITT DOV DD_7	4 000	1629 55	6514 21
	653-0120		EA EA LF LF LF LF TN TN LB SY	THEOM DIMT MADE ADDOM TO 2	9 000	87.40	786 66
	653-0120		EV	THEOM DIMT MADE ADDOW TO 3	4.000	106.62	126.19
	653-1502		LE	THERM COLID TOAT OF 5 TH VEL	110 000	1 23	135 06
	653-1704		T E	THERMO SOLID TRAF SI, SIN TELL	350 000	5.27	2055 45
	653-1804		T E	THERM SOUTH TRAF STRIFE, 24, NO	2640 000	2.07	£200.40
	682-6222		T E	CONDITE NORMERI ED 2 2 TN	2040.000	6 29	24492 16
	682-9950		T E	DIRECTIONAL BODE - 5 IN DIRECTION BODE	1300.000	14.00	10200 00
	700-7000		LIE TOM	ACRICIONAL BORE - 3 IN DIRECTION BORE	1 000	14.00	10200.00
	700-7000		TIN	EDDUTTED MIND CDADE	1.000	622 21	622.22
	700-8000		IN	PERTITION NIMBOON COMMENS	1.000	0.40	022.32
	700-9300		SY	COD	5.000	0.40	42.06
	100 2000		O ±	OUR DINE EDD ODE ODI IOOGE ED OM 30 EDD	1700 000	0.73	43.90
0134				SIGNAL INSTALLATION #3 PULL BOX, PB-7 THERM PVMT MARK, ARROW, TP 2 THERM PVMT MARK, ARROW, TP 3 THERMO SOLID TRAF ST, 5 IN YEL THERM SOLID TRAF STRIPE, 24, WH THERM SOLID TRAF STRIPE, 8, WH CONDUIT, NONMETL, TP 2, 2 IN DIRECTIONAL BORE - 5 IN DIRECTION BORE AGRICULTURAL LIME FERTILIZER MIXED GRADE FERTILIZER NITROGEN CONTENT SOD OUT PLNT FBR OPT CBL, LOOSE TB, SM, 72 FBR	1/00.000	2.57	4369.00
	935-1512		LF	OUT PLNT FBR OPT CBL, DROP, SM, 12 FBR	120.000	2.25	270.00
	935-3206		EA	FBR OPTIC CLOSURE, AERL (SLD), 72 FBR	4.000	910.00	3640.00
0145	935-4010		EA	FIBER OPTIC SPLICE, FUSION	4.000	52.67	210.69
0150	935-5050		EA	FIBER OPTIC PATCH CORD, SM	12.000	6.00	72.00
0155	935-5060		EA	FIBER OPTIC SNOWSHOE	4.000	141.00	564.00
0160	939-2305		EA	OUT PLNT FBR OPT CBL,DROP,SM,12 FBR FBR OPTIC CLOSURE,AERL(SLD),72 FBR FIBER OPTIC SPLICE, FUSION FIBER OPTIC PATCH CORD, SM FIBER OPTIC SNOWSHOE FIELD SWITCH, TYPE C	4.000	1805.25	7221.00
ITEM	TOTAL						463291.13

#### STATE HIGHWAY AGENCY

DATE : 10/19/2015 PAGE : 2

#### TOR DETAIL ESTIMATE

JOB DETAIL ESTIMATE	
INFLATED ITEM TOTAL	463291.14
TOTALS FOR JOB PI0012826	
ESTIMATED COST:  CONSTRUCTION ENGINEERING & INSPECTION ( 5.0 ):  CONTINGENCY PERCENT ( 5.0 ):  ESTIMATED TOTAL:	463291.14 23164.56 24323.13 510778.50

# DEPARTMENT OF TRANSPORTATION STATE OF GEORGIA

#### INTER-DEPARTMENT CORRESPONDENCE

FROM: Nicholas Fields

District Utilities Engineer

DATE: November 9, 2015

TO: Xavier James, Project Manager

SUBJECT: PRELIMINARY UTILITY COST ESTIMATE PI: 00012826 SR 155 / Clairmont Road @ 4 LOC

As requested by your office, we are furnishing you with a Preliminary Cost Estimate for each utility with facilities potentially located with the project limits.

FACILITY OWNER	REIMBURSABLE	NON- REIMBURSABLE	TOTAL
Georgia Power Company	\$135,000,00	\$0.00	\$135,000.00
AT&T	\$0.00	\$0.00	\$0.00
Atlanta Gas Light	\$0.00	\$0.00	\$0.00
Comcast	\$0.00	\$0.00	\$0.00
Clayton County Water and Sewer	\$0.00	\$0.00	\$0.00
Clayton County Department of Transportation and Development	\$0.00	\$0.00	\$0.00
Charter Communication	\$0.00	\$0.00	\$0.00
Verizon	\$0.00	\$0.00	\$0.00
Qwest Communication	\$0.00	\$0.00	\$0.00
TW Telecommunication	\$0.00	\$0.00	\$0.00
Zayo Fiber Solutions	\$0.00	\$0.00	\$0.00
Dukenet Communication	\$0.00	\$0.00	\$0.00
American Traffic Solution	\$0.00	\$0.00	\$0.00
			\$0.00
			\$0.00
			\$0.00
			\$0.00
			\$0.00
			\$0.00
			\$0.00
			\$0.00
TOTAL	\$135,000.00	\$0.00	\$135,000.00

This estimate is based upon the current information. We will provide an updated estimate when the plans are further developed.

If you have any questions, please contact Wade Woodard at 770-986-1117

KZ/NF/SW/LB

Cc: Lee Upkins, State Utilities Engineer

# **Department of Transportation**

# State of Georgia

\_\_\_\_\_

## Interdepartmental Correspondence

FILE R/W Cost Estimate OFFICE Atlanta

DATE December 07, 2015

FROM Phil Copeland, Right of Way Administrator

LaShone Alexander, Right of Way Cost Estimator

TO Xavier James, Project Manager

**SUBJECT** Preliminary Right of Way Cost Estimate

**Project: Dekalb County** 

P.I. No.: 0012826

**Description: Signal Upgrades @ 4 Locations SR 155 (Clairmont Rd)** 

As per your request, attached is a copy of the approved Preliminary Right of Way Cost Estimates on the above referenced projects.

If you have any questions, please contact LaShone Alexander at One Georgia Center 600 West Parkway Street, NW Atlanta, GA 30308, Right of Way Office at (478) 553-1569 or (478) 232-4045.

.

PC:LA Attachments c: File

# GEORGIA DEPARTMENT OF TRANSPORTATION PRELIMINARY ROW COST ESTIMATE SUMMARY

Project: 0012826

12/7/2015

Date:

Revised:	County:		
		0012826	
Description: Signal Ugrades 4 Lo	ocations		
Project Termini:			
			ROW: Varies
Parcels: 4		Required F	ow: Varies
Land and Improvements		\$4,500.00	
Proximity Damage	\$0.00		
Consequential Damage	\$3,000.00		
Cost to Cures	\$0.00		
Trade Fixtures	\$0.00		
Improvements	\$0.00		
Valuation Services		\$25,000.00	
Legal Services		\$40,200.00	
Relocation		\$8,000.00	
Demolition		\$0.00	
Administrative		\$35,500.00	
TOTAL ESTIMATED COSTS		\$113,200.00	
TOTAL ESTIMATED COSTS (ROUNDED)		\$114,000.00	
Preparation Credits Hours	Sign	ature	
Treparation electes floors	Sign	uture	
Prepared By: Sobhone	Alexandor	CG#: 286999	12/07/2015(DATE)
Approved By:	Flexander	CG#: 286999	12/07/2015(DATE)
NOTE: No Market Appreciation is included in this	Preliminary Cost Est	imate	