D.O.T. 66

DEPARTMENT OF TRANSPORTATION **STATE OF GEORGIA**

INTERDEPARTMENT CORRESPONDENCE

FILE

STP-198-1(20) Hall County

OFFICE Preconstruction

P. I. No. 132610

DATE

October 10, 1997

FROM

C. Wayne Hutto, Assistant Director of Preconstruction

TO

SEE DISTRIBUTION

PROJECT CONCEPT REPORT APPROVAL **SUBJECT**

Attached for your files is the approval for subject project.

CWH/cj

Attachment

DISTRIBUTION:

Walker Scott

Bobby Mustin

David Studstill (ATTN: Harvey Keepler)

Jerry Hobbs

Herman Griffin

Marta Rosen (ATTN: Michael Henry)

Marion Waters

Toni Dunagan

Paul Liles

Jim Hitt (Traffic Ops)

Don Mills

Hugh Tyner

INTERDEPARTMENT CORRESPONDENCE

FILE

STP-198-1(20) Hall County

OFFICE Preconstruction

P.I. No. 132610

DATE

September 17, 1997

FROM

Walker W. Scot Ir., P.E., Director of Preconstruction

TO

Wayne Shackelford, Commissioner

PROJECT CONCEPT REPORT **SUBJECT**

This project is the widening and reconstruction of SR 60 from just north of SR 136 to Yellow Creek Road for a total of 6.94km. State Route 60 is a major corridor from the northern Hall County and Lumpkin County areas to the major employment, schools, and shopping centers in the City of Gainesville. This proposed project will widen existing SR \(\)60 to improve operational efficiency and increase capacity in the rapidly growing north Hall County. The existing roadway consists of two, 3.6m lanes with variable width rural shoulders with center turn lanes at various locations. The existing major structure consists of a triple 3.0m x 27.0m concrete box culvert over Squirrel Creek. The existing right-of-way varies from 18.3m to 30.4m. The base year traffic (1999) is 11,600 VPD and the design year traffic (2019) is 19,700 VPD. The posted speed varies from 70km/h to 90km/h and the design speed is 70km/h.

The proposed construction will provide four, 3.6m lanes with a 6.1m raised median for the entire project length. The proposed right-of-way is 40.0m. The existing culvert over Squirrel Creek will be extended to accommodate the proposed widening. Access will be controlled by driveway permit. No design exceptions are required to implement this project. Traffic will be maintained utilizing stage construction.

Environmental concerns include requiring an Environmental Assessment be prepared; possible 4(f) impacts; a COE 404 permit is required; eight (8) possible UST sites impacted; three (3) possible hazardous waste sites impacted; 18 displacements - 11 residences, 6 businesses, and 1 mobile home; a public hearing is required; time saving procedures are not appropriate.

The estimated costs for this project are:

	PROPOSED	APPROVED	PROG DATE	LET DATE
Construction (includes E&C and inflation)	\$6,535,000	\$1,286,000	2000	LR
Right-of-Way	\$1,400,000	\$ 105,000		
Utilities*				

Wayne Shackelford Page 2

STP-198-1(20) Hall September 17, 1997

*LGPA sent 3-20-96 requesting Hall County be responsible for utility relocations.

This project will increase capacity, enhance safety and reduce congestion along this portion of SR 60. This project is in the STIP. I recommend this project concept be approved.

WWS:JDQ/cj

Attachment

CONCUR_

Frank L. Danchetz, P.E., Chief Engineer

APPROVE

Wayne Shackelford, Commissioner



RECEIVED

SEP O 2 1997

PRECONSTRUCTION

FILE:

STP-198-1(20) HALL

P.I. NUMBER 132610

OFFICE: Atlanta, Georgia

DATE:

SEPTEMBER 2, 1997

FROM:

Bob Mustin, Project Review Engineer

TO:

C. Wayne Hutto, Assistant Director of Preconstruction

SUBJECT:

PROJECT CONCEPT REPORT

We have reviewed the concept report submitted July 8, 1997 by the letter from Hugh L. Tyner dated June 30, 1997 and have no comments.

The estimated costs for the project are as follows:

Construction

\$ 4,950,000

Inflation

\$ 495,000

E&C

\$1,090,000

\$ 1,400,000

Right of Way \$ Reimbursable Utilities \$

? (LGPA)

DTM

c: Hugh Tyner - Attention: Tony Bradley

INTERDEPARTMENT CORRESPONDENCE

FILE

STP-198-1 (20) Hall County

OFFICE

Gainesville, GA

P. I. NO. 132610

DATE

June 30, 1997

FROM

Hugh L. Tyner, P. E., District Engineer

TO

Wayne Hutto, Assistant Director of Preconstruction

SUBJECT SUBMITTAL OF PROJECT CONCEPT REPORT

Attached for your review and further handling is a concept report for the above listed project.

If additional information is required, please feel free to contact Tony R. Bradley at (770) 532-5580.

HLT/TRB/dmr

c:w/attachments

Bobby Mustin, Project Review Eng. - Eng. Svcs. David Studstill, State Environmental/Location Eng. Marion Waters, State Traffic Operations Eng.

INTERDEPARTMENT CORRESPONDENCE

FILE

STP-198-1 (20) Hall County

OFFICE

Gainesville, GA

P. I. NO. 132610

DATE

June 30, 1997

FROM

Hugh L. Tyner, P. E., District Engineer

TO

Wayne Hutto, Assistant Director of Preconstruction

SUBMITTAL OF PROJECT CONCEPT REPORT **SUBJECT**

Attached for your review and further handling is a concept report for the above listed project.

If additional information is required, please feel free to contact Tony R. Bradley at (770) 532-5580.

HLT/TRB/dmr

c:w/attachments

Bobby Mustin, Project Review Eng. - Eng. Svcs. David Studstill, State Environmental/Location Eng.

Marion Waters, State Traffic Operations Eng.


PROJECT CONCEPT REPORT

STP-198-1(20) HALL COUNTY

U.S. ROUTE NO: STATE ROUTE NO: 60 GADOT P.I. NO: 132610 Date of Report: June 30, 1997

	RECOMMENDATION FOR APPROVAL
7-7-97 DATE	Hugh L. Tyner, District Engineer
DATE	State Environmental Engineer
DATE	State Traffic Operations Engineer
DATE	Project Review Engineer
DATE	State Bridge Engineer

PAGE 2 P.I. NO: 132610 20)



PAGE 3

P.I. NO: 132610

PROJECT NUMBER: STP-198-1(20)

PROJECT LOCATION & DESCRIPTION

Project STP-198-1(20) Hall County is located on SR 60 approximately 1.61 Kilometers northwest of the city of Gainesville. Beginning at the end of the existing four lane section just north of S.R. 136 and extending along the existing S.R. 60 to the intersection of Yellow Creek Road (CR 158).

PROJECT LENGTH: 6.936 KILOMETERS

	TRAF	FIC	
CUR	RENT	PROJ	ECTED
YEAR	AADT	YEAR	AADT
1999	<u>11600</u>	2019	<u> 19700</u>

PDP CLASSIFICATION	FUNCTIONAL CLASSIFICATION
MAJOR	MINOR ARTERIAL

NON CA ()	CA (Y)	EXEMPT ()	N/A ()
NON-CA ()	CA (A)	EVENLT ()	N/A ()

PAGE 4

P.I. NO: 132610

PROJECT NEED & PURPOSE

This project will widen the existing two lane facility to a 4 lane raised median facility. S.R. 60 is a major link from the northern Hall County and Lumpkin County areas to the major employment, schools and shopping centers in the city of Gainesville. S.R. 60 includes several churches, businesses, schools and a maj or poultry processing plant. This project will greatly improve the capacity and safety in the rapidly growing north Hall County.

EXISTING ROADWAY

TYPICAL SECTION: 2 each - 3.6 m lanes w/var. width graded shoulders with center turn lanes at various intersections.

R/W WIDTH

18.3 - 30.4 Meters

POSTED SPEED

MAX DEGREE OF CURVE

MAXIMUM GRADE

70 and 90 KPH

unknown

unknown

MAJOR STRUCTURES:

1. Triple 10'X 9'X101' Concrete box culvert crossing Squirrel Creek.

PROPOSED ROADWAY

TYPICAL SECTION: two 3.6m lanes in each direction with 6.0m raised median urban section.

DESIGN SPEED

MAX DEGREE OF CURVE

MAX GRADE

70 Km/h

ALLOWABLE: 305 R

ALLOWABLE: 7.00 %

PROPOSED: 305 R

PROPOSED: 7.00 %

MAJOR STRUCTURES: Extend existing culvert.

PAGE 5 P.I. NO: 132610

PROPOSED RIGHT OF WAY

R/W WIDTH

DISPLACEMENTS

40 Meters

RES: <u>11</u> BUS: <u>6</u> M.H.: <u>1</u>

TYPE OF ACCESS CONTROL: By permit

NUMBER OF PARCELS: 187

COORDINATION

CONCEPT TEAM MEETING DATE:

LOCATION INSPECTION DATE: June 20, 1997

PERMITS REQUIRED (4f, COE, 404, etc.): possible 45 and 404

LEVEL OF PUBLIC INVOLVEMENT: Public Hearing

TIME SAVING PROCEDURES APPROPRIATE: No

OTHER PROJECT IN THE AREA: None

MISCELLANEOUS

TRAFFIC CONTROL DURING CONSTRUCTION: Traffic to be maintained.

LEVEL OF ENVIRONMENTAL ANALYSIS: Environmental Assessment

DESIGN VARATIONS REQUIRED:	YES	NO	UNDETERMINED
SUBST HORIZ ALIGNMENT	()	(X)	()
SUBST ROADWAY WIDTH	()	(X)	()
SUBST SHOULDER WIDTH	()	(X)	()
SUBST VERT GRADES	()	()	(X)
SUBST CROSS SLOPES	()	(X)	()
SUBST STOPPING SIGHT DIST	()	(X)	()
SUBST SUPERELEV RATES	()	(X)	()
SUBST HORIZ CLEARANCE	()	(X)	()
SUBST SPEED DESIGN	()	(X)	()
SUBST VERTICAL CLEARANCE	()	(X)	()
SUBST BRIDGE WIDTH	()	(X)	()
SUBST BR STRUCT CAPACITY	()	(X)	()

UNDERGROUND STORAGE TANKS: 8 possible sites

HAZARDOUS SITES: 3 possible sites

ALTERNATIVES CONSIDERED

1. Widen from two lanes to three, rejected due to projected traffic volumes.

2. No Build

ESTIMATED COST					
CONSTRUCTION:	\$	4,949,800	RIGHT-OF-WAY:	\$	1,400,000
E & C (10) :	\$	494,980	ACQUIRED BY :	DOT	
INFLATION :	\$	1,361,195	UTILITIES :	\$	0
			ADJUSTED BY :	LGPA	
TOTAL (reno	RUCTION COST:	\$6,805,975		

P.I. NO: 132610

PRELIMINARY COST ESTIMATE

PROJECT NUMBER: STP-198-1(20)

COUNTY: Hall

DATE: June 30, 1997

ESTIMATED LETTING DATE: Long Range

PREPARED BY: Tony R. Bradley PROJECT LENGTH (KILOMETERS): 6.936

() PROGRAMMING PROCESS (X) CONCEPT DEVELOPMENT () DURING PROJECT DEV.


PROJECT COST		
A. RIGHT-TO-WAY: DOT		
1. PROPERTY (LAND & EASEMENT)	\$	130,000
2. DISPLACEMENTS; RES:11, BUS;6, M.H.:1	\$	1,270,000
3. OTHER COST (ADM./COST, INFLATION)	\$	0 .
SUBTOTAL: A	\$	1,400,000
B. REIMBURSABLE UTILITIES: LGPA		
1. RAILROAD	\$. 0
2. TRANSMISSION LINES	\$	0
3. SERVICES	\$	0
SUBTOTAL: E	\$ \$	0
C. CONSTRUCTION:		
1. MAJOR STRUCTURES		
a. RETAINING WALLS	\$	0
b. BRIDGES	\$	0
c. DETOURS BRIDGES	\$	0
d. BOX CULVERTS - TRIPLE 10'X 9' EXTEND EXIST.	\$	200,000
SUBTOTAL:C-1	<u>\$</u>	200,000
2. GRADING AND DRAINAGE:		
a. EARTHWORK	\$	800,000
b. DRAINAGE:		
1) Cross Drain Pipe (exclude box culverts)	\$	500,000
2) Curb and Gutter	\$	910,000
3) Longitudinal System(include catch basins)	\$	320,000
SUBTOTAL: C-2	\$	2,530,000

PAGE 8 P.I. NO: 132610

PROJECT COST		
3. BASE AND PAVING:		
a. AGGREGATE BASE 38,000 MG @ \$17.00	\$	500,000
b. ASPHALT PAVING: Surface 12,000 MG \$420,000		
Binder 16,000 MG \$560,000		
Base 14,000 MG \$490,000		
SUBTOTAL:C-3.b	\$	1,470,000
c. CONCRETE PAVING	\$	0
d. OTHER	\$	0
SUBTOTAL:C-3	\$	1,970,000
4. LUMP ITEMS:		
a. TRAFFIC CONTROL	\$	18,000
b. CLEARING AND GRUBBING	\$	24,000
c. LANDSCAPING	\$	15,500
d. EROSION CONTROL	\$	45,500
e. DETOURS	\$	10,000
SUBTOTAL:C-4	\$	113,000
5. MISCELLANEOUS:		
a. LIGHTING	\$. 0
b. SIGNING - STRIPING - SIGNAL		98,300
c. GUARDRAIL		38,500
d. SIDEWALK - MEDIAN BARRIER	\$	0
SUBTOTAL:C-5	\$	136,800
6. SPECIAL FEATURES SUBTOTAL:C-6	\$	0

ESTIMATE SUMM	ARY
A. RIGHT-OF-WAY	\$ 1,400,0
B. REIMBURSABLE UTILITIES	\$
C. CONSTRUCTION	
1. MAJOR STRUCTURES	\$ 200,000
2. GRADING AND DRAINAGE	\$ 2,530,000
3. BASE AND PAVING	\$ 1,970,000
4. LUMP ITEMS	\$ 113,000
5. MISCELLANEOUS	\$ 136,800
6. SPECIAL FEATURES	\$ 0
SUBTOTAL CONSTRUCTION COST	\$ 4,949,800
E. & C. (10%)	\$ 494,980
INFLATION (5% PER YEAR)	\$ 1,361,195
NUMBER OF YEARS 5	
TOTAL CONSTRUCTION COST	\$ 6,805,9
GRAND TOTAL PROJECT COST	\$ 8,205,9

TYPICAL SECTION



STP-198-1(20) P.I. NO 132610 HALL CO.

RECEIVED

JUL US 1997

PRECONSTRUCTION

INTERDEPARTMENT CORRESPONDENCE

FILE

STP-198-1 (20) Hall County

OFFICE

Gainesville, GA

P. I. NO. 132610

DATE

June 30, 1997

FROM

Hugh L. Tyner, P. E., District Engineer

TO

Wayne Hutto, Assistant Director of Preconstruction

SUBJECT SUBMITTAL OF PROJECT CONCEPT REPORT

Attached for your review and further handling is a concept report for the above listed project.

If additional information is required, please feel free to contact Tony R. Bradley at (770) 532-5580.

HLT/TRB/dmr

c:w/attachments

Bobby Mustin, Project Review Eng. - Eng. Svcs. David Studstill, State Environmental/Location Eng. Marion Waters, State Traffic Operations Eng.

PROJECT CONCEPT REPORT

STP-198-1(20) HALL COUNTY

U.S. ROUTE NO: STATE ROUTE NO: 60 GADOT P.I. NO: 132610 Date of Report: June 30, 1997

	RECOMMENDATION FOR APPROVAL
7-7-97 DATE	Hugh L. Tyner, District Engineer
DATE	State Environmental Engineer
DATE	State Traffic Operations Engineer
DATE	Project Review Engineer
DATE	State Bridge Engineer