

ORIGINAL TO GENERAL FILES

D.O.T. 66

**DEPARTMENT OF TRANSPORTATION
STATE OF GEORGIA**

INTERDEPARTMENT CORRESPONDENCE

FILE NH-IM-75-3(188) Cherokee County **OFFICE** Preconstruction
P. I. No. 610740
DATE September 13, 2001
FROM *CWH*
C. Wayne Hutto, Assistant Director of Preconstruction
TO SEE DISTRIBUTION

SUBJECT REVISED PROJECT CONCEPT REPORT APPROVAL

Attached for your files is the approval for subject project.

CWH/cj

Attachment

DISTRIBUTION:

Tom Turner
David Mulling
Harvey Keepler
Jerry Hobbs
Herman Griffin
Michael Henry
Phillip Allen
Marta Rosen
Jimmy Chambers
Kent Sager
BOARD MEMBER

DEPARTMENT OF TRANSPORTATION
STATE OF GEORGIA

INTERDEPARTMENT CORRESPONDENCE

FILE NH-IM-75-3(188) *Cherokee* OFFICE Road and Airport Design
 P.I. No.: 610740 DATE May 22, 2001

FROM James A. Kennerly, State Road and Airport Design Engineer *James A. Kennerly*

TO C. Wayne Hutto, Assistant Director of Preconstruction *C. Wayne Hutto*

SUBJECT **Revised Project Concept Report** JUL 11 2001

Attached is the original copy of the revised Concept Report for your further handling for approval in accordance with the Plan Development Process (PDP).

The original concept proposed a typical section which consisted of 3 lanes in each direction separated by a 20 ft. raised median with urban shoulders is revised to consist of 2 lanes in each direction separated by a 20 ft. raised median with urban shoulders.



The revised concept as presented herein and submitted for approval is consistent with that which is included in the Regional Transportation Improvement Program (RTP) and/or the State Transportation Improvement Program (STIP).

By receipt of this letter this office requests that the Office of Planning provide the Office of Road Design a letter of conformity to AQE standards for this project.

DATE 7-25-01

Marta Rosen
State Transportation Planning Administrator

- Xc: David Mulling, Project Review Engineer
- Harvey Keepler, State Environmental/Location Engineer
- Marion Waters, State Traffic Operations Engineer
- Marta Rosen, State Transportation Planning Administrator
- Herman Griffen, State Transportation Programming Engineer
- Kent Sager, District Engineer
- Paul Liles, State Bridge Design Engineer



DEPARTMENT OF TRANSPORTATION
STATE OF GEORGIA


INTERDEPARTMENTAL CORRESPONDENCE

OFFICE Planning

DATE July 23, 2001

File

FROM


Marta V. Rosen, State Transportation Planning Administrator

TO

James A. Kennerly, State Road and Airport Design Engineer
Attn. Jason McCook

SUBJECT

REVISED PROJECT CONCEPT REPORT CONFORMITY - CERTIFICATION FOR
REVISED CONCEPT REPORT – Project NH-IM-75-3(188) Cherokee County, PI #
610740, I-75 @ SR 92. Interchange reconstruction.

The Office of Planning is providing this letter of certification as defined in the Plan Development Process Manual of Guidance. The revised project concept, consisting of two lanes in each direction separated by a twenty foot raised median with urban shoulders, is in conformance with the adopted Air Quality Model of the Atlanta Regional Transportation Plan and the State Transportation Improvement Program.

By copy of this letter, the project revised concept is found to conform to the Atlanta Regional Transportation Plan based on the July 23, 2001, review. If any changes occur to the revised concept, please notify this office immediately. If you have any questions, please call Roxana Ene at 404-463-4377.

MVR:re

cc: Tom Turner

REVISED PROJECT CONCEPT REPORT

Need and Purpose: Due to recent growth in southeast Cherokee County, a transportation study was conducted to assess the growth potential for southeast Cherokee County. A program for transportation improvements to meet the needs of this growth was a result of this study. Among other projects, this study supported the recommendation that improvements be made to the interchange at S.R. 92 and I-75 in Cherokee County. The proposed project will improve the capacity of S.R. 92 while providing a safer environment for the motorist, with reduced travel and congestion.

Project location: This project is the reconstruction of the S.R. 92 at I-75 interchange and the widening of S.R. 92 from Cowan Road in Cobb County to Northpoint Parkway in Cherokee County. The beginning Milelog is at M.P. 14.29 in Cobb County on S.R. 92 and the ending M.P. is M.P. 0.41 in Cherokee County.

Description of the approved concept: S.R. 92 widening and Interchange reconstruction of S.R. 92 at I-75.

PDP Classification:

Full Oversight (x), Exempt(), SF(), Other ()

Functional Classification: Rural Minor Arterial

U. S. Route Number(s): I-75 **State Route Number(s):** S.R. 401, S.R. 92

Traffic (AADT) as shown in the approved concept:

Current Year: 21700 (1995) Design Year: 36900 (2015)

Proposed features to be revised: The proposed typical section to be revised consisted of a six lane urban section with a twenty foot (20') raised median with three (3) lanes in each direction

Describe the revised feature(s) to be approved: The revised typical section would consist of a eight lane urban section with a twenty foot (20') with two lanes in each direction and dual left turns.

Updated traffic data (AADT):

Current Year: 23,500 (2000)
Design Year: 40,000 (2020)

Programmed/Schedule:

P.E. 3-31-92

R/W: 2001

Construction: 2003

Revised cost estimates:

1. Construction cost including inflation and E&C, \$ 5,
2. Right-of-way, and
3. Utilities

Is the project located in a Non-attainment area? Yes

The typical section for the current concept of three lanes in each direction would not be in compliance with the conforming plan model which consist of two lanes in each direction. This project is scheduled to open in model year 2005.

Recommendation: Recommend that the proposed revision to the concept be approved for implementation.

Attachments:


Sketch Map,
Cost Estimate,
Conforming plan's network schematics showing thru lanes

Concur: Thomas R. Linn
Director of Preconstruction

Approve: Floyd Moore
Division Administrator, FHWA

Approve: J. L. Carthy
Chief Engineer

Project Location



Cost Estimate for NH-IM-75-3-(188), Cherokee Co.,
P.I. NO. 610740

ITEM	DESCRIPTION	QUANTITY	COST
UNITS	WT. AVG.		

ROADWAY ITEMS

150-5010	TRAFFIC CONTROL, PORTABLE IMPACT ATTENUATOR		
EA	20469.708181	10	\$204697.08
153-1300	FIELD ENGINEERS OFFICE TP 3		
EA	54010.12525	1	\$54010.13
207-0203	FOUND BKFILL MATL, TP II		
M3	44.516162671	200	\$8903.23
210-0100	GRADING COMPLETE -IM-75-3(188)		
LS	340416.79140	LUMP	\$340416.79
310-5060	GR AGGR BASE CRS, 150 MM, INCL MATL		
M2	6.7269614943	625	\$4204.35
310-5080	GR AGGR BASE CRS, 200 MM, INCL MATL		
M2	9.8367299222	5800	\$57053.03
310-5100	GR AGGR BASE CRS, 250 MM, INCL MATL		
M2	9.6087441302	10300	\$98970.06
318-3000	AGGREGATE SURFACE COURSE		
MG	15.522649017	2000	\$31045.30
402-1812	RECYCLED ASPH CONC LEVELING, INCL BITUM MATL & H LIME		
MG	36.524236843	13850	\$505860.68
402-3121	RECYCLED ASPH CONC 12.5 MM SUPERPAVE, GP 2 ONLY, INCL BITUM		
MG	36.661659161	6500	\$238300.78
402-3190	RECYCLED ASPH CONC 19 MM SUPERPAVE, GP 1 OR 2, INCL BITUM		
MG	37.316896254	3600	\$134340.83
402-3250	RECYCLED ASPH CONC 25 MM SUPERPAVE, GP 1 OR 2, INCL BITUM		
MG	39.659301765	6100	\$241921.74
433-1200	REINF CONC APPROACH SLAB, INCL SLOPED EDGE		
M2	118.11073855	700	\$82677.52
441-0016	DRIVEWAY CONCRETE, 150 MM THK		
M2	31.582680151	400	\$12633.07
441-0018	DRIVEWAY CONCRETE, 200 MM THK		
M2	40.304731652	370	\$14912.75
441-0104	CONC SIDEWALK, 100 MM		
M2	22.875763784	3660	\$83725.30
441-0204	PLAIN CONC DITCH PAVING, 100 MM		
M2	28.472794067	600	\$17083.68
441-0301	CONC SPILLWAY, TP 1		
EA	1268.1819711	2	\$2536.36
441-0740	CONCRETE MEDIAN, 100 MM		
M2	23.320020571	3500	\$81620.07
441-3999	CONCRETE V GUTTER		
LM1	59.429732202	185	\$10994.50
441-4020	CONC VALLEY GUTTER, 150 MM		
M2	33.427473371	121	\$4044.72
441-4030	CONC VALLEY GUTTER, 200 MM		
M2	41.865536476	340	\$14234.28
441-5002	CONCRETE HEADER CURB, 150 MM, TP 2		
LM1	34.963626157	704	\$24614.39

441-6222	CONC CURB & GUTTER, 200 MM X 750 MM, TP 2		
LM1	33.025602248	3900	\$128799.85
550-1180	STORM DRAIN PIPE, 450 MM, H 0.3 - 3 M		
LM1	79.471708344	1090	\$86624.16
550-1240	STORM DRAIN PIPE, 600 MM, H 0.3 - 3 M		
LM1	105.28304832	90	\$9475.47
550-2180	SIDE DRAIN PIPE, 450 MM, H 0.3 - 3 M		
LM1	67.739099635	0	\$0.00
550-4124	FLARED END SECTION 600 MM, SIDE DRAIN		
EA	292.03121951	3	\$876.09
550-4218	FLARED END SECTION 450 MM, STORM DRAIN		
EA	420.88121088	18	\$7575.86
573-2006	UNDDR PIPE INCL DRAINAGE AGGR, 150 MM		
LM1	31.369353945	600	\$18821.61
576-1018	SLOPE DRAIN PIPE, 450 MM		
LM1	79.851518987	21	\$1676.88
611-3010	RECONSTR DROP INLET, GROUP 1		
EA	828.44257703	3	\$2485.33
611-3030	RECONSTR STORM SEW MANHOLE, TP 1		
EA	1346.7371428	3	\$4040.21
622-1032	PRECAST CONCRETE MEDIAN BARRIER, METHOD 2		
LM1	71.430629515	1140	\$81430.92
634-1200	RIGHT OF WAY MARKER		
EA	70.211998287	69	\$4844.63
641-1100	GUARDRAIL, TP T		
LM1	120.53302396	90	\$10847.97
641-1200	GUARDRAIL, TP W		
LM1	34.901273600	1660	\$57936.11
641-5001	GUARDRAIL ANCHORAGE, TP 1		
EA	427.52703261	8	\$3420.22
641-5012	GUARDRAIL ANCHORAGE, TP 12		
EA	1457.2009984	8	\$11657.61
668-1100	CATCH BASIN, GP 1		
EA	1737.6966443	38	\$66032.47
668-1110	CATCH BASIN, GP 1, ADDL DEPTH		
LM1	526.67657210	4	\$2106.71
668-2100	DROP INLET, GP 1		
EA	1968.6354527	5	\$9843.18
668-4300	STORM SEWER MANHOLE, TP 1		
EA	1683.0230246	1	\$1683.02

Section SUB TOTAL \$2778978.97

EROSION CONTROL

163-0230	TEMPORARY GRASS		
M2	133.05490971	35	\$4656.92
163-0235	TEMPORARY MULCH		
M2	488.81503211	7	\$3421.71
163-0520	CONSTRUCT AND REMOVE TEMPORARY PIPE SLOPE DRAIN		
LM1	28.036273475	9	\$252.33
165-0010	MAINTENANCE OF TEMPORARY SILT FENCE, TP A		
LM1	4.3054478890	5500	\$23679.96
165-0020	MAINTENANCE OF TEMPORARY SILT FENCE, TP B		
LM1	3.3291754153	275	\$915.52

165-0070	MAINTENANCE OF TEMPORARY BALED STRAW EROSION CHECK		
LM1	5.5554457609	1250	\$6944.31
165-0085	MAINTENANCE OF SILT CONTROL GATE, TYPE 1		
EA	207.11882352	2800	\$579932.71
165-0087	MAINTENANCE OF SILT CONTROL GATE, TYPE 3		
EA	181.69758064	9	\$1635.28
167-0100	WATER QUALITY MONITORING		
MO	2176.7582352	30	\$65302.75
167-0200	WATER QUALITY SAMPLING		
EA	342.62080924	1	\$342.62
171-0010	TEMPORARY SILT FENCE, TYPE A		
LM1	8.3718424865	550	\$4604.51
171-0030	TEMPORARY SILT FENCE, TYPE C		
LM1	14.218373338	2500	\$35545.93
500-3101	CLASS A CONCRETE		
M3	457.23250206	45	\$20575.46
511-1000	BAR REINF STEEL		
KG	1.2939633658	3350	\$4334.78
603-2181	STN DUMPED RIP RAP, TP 3, 450 MM		
M2	36.465722337	85	\$3099.59
603-2182	STN DUMPED RIP RAP, TP 3, 600 MM		
M2	38.707436889	50	\$1935.37
603-2186	STN DUMPED RIP RAP, TP 3, 900 MM		
M2	53.405339805	270	\$14419.44
603-7000	PLASTIC FILTER FABRIC		
M2	3.2262999013	300	\$967.89
700-6900	PERMANENT GRASSING		
KG	62.472284616	300	\$18741.69
700-7000	AGRICULTURAL LIME		
MG	58.150577586	30	\$1744.52
700-8000	FERTILIZER MIXED GRADE		
MG	257.18103641	8	\$2057.45
700-8100	FERTILIZER NITROGEN CONTENT		
KG	2.8808540982	170	\$489.75
700-9100	BLOCK SOD		
M2	8.9994462390	1039	\$9350.42
715-2200	BITUMINOUS TREATED ROVING, WATERWAYS		
M2	3.2401342657	60	\$194.41
716-2000	EROSION CONTROL MATS, SLOPES		
M2	2.0924560565	14510	\$30361.54

Section SUB TOTAL \$835506.84

SIGNING & MARKING

610-6515	REM HIGHWAY SIGN, STD		
EA	92.829326145	7	\$649.81
611-5551	RESET SIGN		
EA	539.21878378	7	\$3774.53
636-1029	HIGHWAY SIGNS, TP 1 MATL, REFL SHEETING, TP 3		
M2	194.23057835	106	\$20588.44
636-2030	GALV STEEL POSTS, TP 3		
LM1	15.684568886	530	\$8312.82
636-2040	GALV STEEL POSTS, TP 4		
LM1	20.545869660	10	\$205.46

639-2002	STEEL WIRE STRAND CABLE, 9.53 MM		
LM1	10.665617843	240	\$2559.75
639-3002	STEEL STRAIN POLE, TP II		
EA	4010.3043478	6	\$24061.83
653-0110	THERMOPLASTIC PVMT MARKING, ARROW, TP 1		
EA	56.615626822	2	\$113.23
653-0120	THERMOPLASTIC PVMT MARKING, ARROW, TP 2		
EA	56.379704208	77	\$4341.24
653-0130	THERMOPLASTIC PVMT MARKING, ARROW, TP 3		
EA	98.722572614	3	\$296.17
653-0210	THERMOPLASTIC PVMT MARKING, WORD, TP 1		
EA	79.869696691	43	\$3434.40
653-1501	THERMOPLASTIC SOLID TRAFFIC STRIPE, 125 MM, WHITE		
LM1	0.6451429633	800	\$516.11
653-1502	THERMOPLASTIC SOLID TRAFFIC STRIPE, 125 MM, YELLOW		
LM1	0.6560949224	500	\$328.05
653-1704	THERMOPLASTIC SOLID TRAFFIC STRIPE, 600 MM, WHITE		
LM1	11.422665450	140	\$1599.17
653-1810	THERMOPLASTIC SOLID TRAFFIC STRIPE, 250 MM, WHITE		
LM1	2.9423344974	1030	\$3030.60
653-3501	THERMOPLASTIC SKIP TRAFFIC STRIPE, 125 MM, WHITE		
GLM1	0.4401038763	3810	\$1676.80
653-3502	THERMOPLASTIC SKIP TRAFFIC STRIPE, 125 MM, YELLOW		
GLM1	0.4522036323	320	\$144.71
653-6004	THERMOPLASTIC TRAF STRIPING, WHITE		
M2	2.8662581293	380	\$1089.18
653-6006	THERMOPLASTIC TRAF STRIPING, YELLOW		
M2	2.6110258103	810	\$2114.93
654-1001	RAISED PVMT MARKERS TP 1		
EA	2.6140631409	80	\$209.13
654-1002	RAISED PVMT MARKERS TP 2		
EA	2.4886032912	870	\$2165.08

Section SUB TOTAL \$81211.43

BRIDGE ITEMS

441-0004	CONC SLOPE PAV, 100 MM		
M2	37.539785093	376	\$14114.96
500-0100	GROOVED CONCRETE		
M2	4.4159903952	726	\$3206.01
500-1006	SUPERSTR CONCRETE, CL AA, BR NO - (LT/RT) (223)		
LS	299631.72	LUMP	\$299631.72
500-3101	CLASS A CONCRETE		
M3	457.23250206	237	\$108364.10
501-3000	STR STEEL, BR NO - (LT/RT) (223)		
LS	689317.74	LUMP	\$689317.74
511-1000	BAR REINF STEEL		
KG	1.2939633658	16969	\$21957.26
511-3000	SUPERSTR REINF STEEL, BR NO -1		
LS	52767.86	LUMP	\$52767.86
520-1125	PILING IN PLACE, STEEL H, HP 310 X 79		
LM1	91.669034486	288	\$26400.68
518-1000	RAISE EXISTING BRIDGE, STA. 85+411.955		
LS	145010	LUMP	\$145010.00

520-4125 LOAD TEST, STEEL H, HP 310 X 79
EA 21.202857142 1 \$21.20
535-1005 PAINT EXIST STEEL STRUCTURE, STA. 85+411.955
LS 75145.217391 0 \$0.00
643-1152 CH LK FENCE, ZC COAT, 1.8 M, 9 GA
LM1 46.248341064 192 \$8879.68

Section SUB TOTAL \$1369671.22


Project Cost \$5065368.46

10% E&C \$506536.85

5% Inflation/year(1) \$278595.27

Total Const. Cost \$5850500.58

SR 92 @ I-75 North: 2025 Network



EXISTING LANE CONFIGURATION

CH AR

610740'
NETWORK YR 2005